



ESP Associates, P.A.

engineering • surveying • planning
P.O. Box 7030 3475 Lakemont Blvd.
Charlotte, NC 28241 Fort Mill, SC 29708
P - 704.583.4949 F - 803.802.2440
F - 704.583.4950 F - 803.802.2515
www.espassociates.com

This drawing and/or the design shown are the property of ESP Associates, P.A. The reproduction, alteration, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.
ESP Associates, P.A.

CLIENT



Trotter Builders
1515 Mockingbird Lane, Suite 900
Charlotte, NC 28209

PROJECT

North Community House Residences


SHEET TITLE

Technical Data Sheet

Petition 2013-098 "For Public Hearing"

PROJECT LOCATION *Charlotte, North Carolina*

GRAPHIC SCALE



PROJECT NO	BR19.100		
DRAWING	BR19.100_ Concept Sketch Plan		
DATE	09-20-2013		
DRAWN BY	GW		
CHECKED BY	PT		
AGENCY / SUBMITTAL REVISION			
NO.	DATE	BY	REVISION
1	12/20/13	GW	staff comments



Vicinity Map

Not to Scale



Site Data:

Parcels:	22322298
Parcel Acreage (Gross):	+/- 10.3 acres
Acreage in ROW:	+/- 2.5 acres
Site Acreage (Net):	+/- 7.8 acres
Zoning:	
Existing:	R-3
Proposed:	UR-3 (CD)
Total Residential Units:	Up to 200 Units (2 Buildings)
Floor Area Ratio Proposed:	.6
Floor Area Ratio Maximum:	up to 2.0
Uses:	
Existing:	Vacant
Proposed:	Multi-Family Residential Apartments


General Notes

1. Base information obtained from ALTA/ACSM Land Title Survey of Parcel 223-222-98 Endhaven Lane, dated 10-22-13, and as applicable Mecklenburg County GIS Data, which should be verified for accuracy.

Site Legend

- Property Line
- ⊙ Site Access
- - - Public Street R.O.W.
- - - Private Street

Petition 2013-098 RZ-1



TAX ID# 223-481-03
JAMES F. DONOGHUE, BISHOP
OF THE ROMAN CATHOLIC
DIOCESE OF CHARLOTTE, NC
ZONED MX-2 & R-3

TAX ID# 223-481-01
JAMES F. DONOGHUE, BISHOP
OF THE ROMAN CATHOLIC
DIOCESE OF CHARLOTTE, NC
ZONED MX-2 & R-3

TAX ID# 223-242-48
SHIRLEY S. JAMES,
TRUSTEE OF THE SHIRLEY
S. JAMES LIVING TRUST
ZONED R-3

TAX ID# 223-242-03
JORGE AND DONNA DASILVA
ZONED R-3

TAX ID# 223-242-02
LISA AND COURTNEY RIDER
ZONED R-3

TAX ID# 223-242-01
PAUL AND MARGARET BOVA
ZONED R-3

TAX ID# 223-231-99
TORINGDON FUTURE
DEVELOPMENT LLC
ZONED CC

TAX ID# 223-231-61
TORINGDON FUTURE
DEVELOPMENT LLC
ZONED CC

TAX ID# 223-231-60
TORINGDON FUTURE
DEVELOPMENT LLC
ZONED CC

TAX ID# 223-231-59
TORINGDON FUTURE
DEVELOPMENT LLC
ZONED CC

TAX ID# 223-161-05
THE BISSELL COMPANY, INC.
ZONED O-3 (CD)

TAX ID# 223-161-02
BALLANTYNE EAST, LLC
ZONED O-3 (CD)

TAX ID# 223-501-50
BALLANTYNE EAST, LLC
ZONED O-3 (CD)

NORTH



ESP Associates, P.A.
 engineering • surveying • planning
 P.O. Box 7030 3475 Lakemont Blvd.
 Charlotte, NC 28241 Fort Mill, SC 29708
 P - 704.583.4949 P - 803.802.2410
 F - 704.583.4950 F - 803.802.2515
 www.espassociates.com

This drawing and/or the design shown are the property of ESP Associates, P.A. The reproduction alteration, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action. ESP Associates, P.A.

CLIENT



Trotter Builders
 1515 Mockingbird Lane, Suite 900
 Charlotte, NC 28209

PROJECT

North Community House Residences


SHEET TITLE

Conceptual Site Plan

Petition 2013-098 "For Public Hearing"

PROJECT LOCATION *Charlotte, North Carolina*

GRAPHIC SCALE



(IN FEET)
 1 inch = 60 ft.

PROJECT NO **BR19.100**

DRAWING **BR19.100_Concept Sketch Plan**

DATE **09-20-2013**

DRAWN BY **GAW**

CHECKED BY **PT**

AGENCY / SUBMITTAL REVISION

NO.	DATE	BY	REVISION
1	12/20/13	GW	staff comments



Vicinity Map

Not to Scale



Site Data:

Parcels:	22322298
Parcel Acreage (Gross):	+/- 10.3 acres
Acreage in ROW:	+/- 2.5 acres
Site Acreage (Net):	+/- 7.8 acres
Zoning:	R-3
Existing:	R-3
Proposed:	UR-3 (CD)
Total Residential Units:	Up to 200 Units (2 Buildings)
Floor Area Ratio Proposed:	.6
Floor Area Ratio Maximum:	up to 2.0
Uses:	Vacant
Existing:	Multi-Family Residential Apartments
Proposed:	

General Notes:

1. Base information obtained from ALTA/ACSM Land Title Survey of Parcel 223-222-98 Endhaven Lane, dated 10-22-13, and as applicable Mecklenburg County GIS Data, which should be verified for accuracy.

Legend

Property Line	—————
Proposed R.O.W.	- - - - -
Underground Detention	—————
Tree Save	
Sidewalk	
Crosswalk	
Site Access	



Note:
 This graphic is intended only to illustrate a conceptual site plan. The building configuration, parking, access points, plantings, and other site elements are subject to final engineering and will be finalized during permitting of the project. The Planning Director or his/her designee may approve an alternate design that meets the intent of the plan shown.

RZ-2



DEVELOPMENT STANDARDS

General Provisions:

These Development Standards form a part of the Technical Data Sheet associated with the Rezoning Petition filed by Trotter Builders, William Trotter Company (the "Petitioner") to rezone an approximate 10.3 acre site located at the southeastern quadrant of Endhaven Lane and the future extension of North Community House Road (the "Site").

The purpose of this Petition is to request rezoning of the Site to the UR-3 (CD) Zoning District to accommodate the construction of up to 200 Multi-Family Dwelling Rental Apartment Units. UR-3 Zoning will enable the Petitioner to develop the Site in a manner that will emphasize the Site's unique features as a property located on the edge of the "Ballantyne Center" as identified in the City of Charlotte's CCW- Centers, Corridors and Wedges Policy Plan Document, creating a harmonious transition between the project and adjoining school properties to the north and east while providing essential right of way to be dedicated (+/- 2.5 Acres) that will be utilized to facilitate significant traffic infrastructure improvements (by others) connecting the Site to Ballantyne's work force and employment center through the extension of future North Community House Road from the Endhaven Lane intersection, across Interstate-485 into Ballantyne.

Unless the Technical Data Sheet or these Development Standards establish more stringent standards, the regulations established under the Ordinance for the UR-3 Zoning District shall govern all development taking place on the Site, subject to the development standards set out herein.

The development depicted on the Conceptual Site Plan is intended to reflect the arrangement of proposed uses on the Site, but the final configurations, placement and sizes of individual Site elements may be altered or modified so long as the maximum building envelope lines and intensity limitations established on the Technical Data Sheet (TDS) are not violated and the proposed alterations or modifications do not exceed the parameters established under these Development Standards and under the Ordinance for the UR-3 Zoning District. However, any alterations or modifications which, in the opinion of the Planning Director, substantially alter the character of the development or significantly alter the Technical Data Sheet or its respective conditions as well as any changes which increase the intensity of development shall not be deemed to be minor and may only be made in accordance with the provisions of Subsections 6.207(1) or (2) of the Ordinance, as applicable.

1. Permitted Uses: The Site may be developed with up to 200 multi-family rental residential apartment dwelling units together with accessory structures as allowed in the UR-3 zoning district.

2. Transportation: Vehicular access to the Site will be provided from both Community House Road and Endhaven Lane as generally depicted on the Technical Data Sheet.

A. Petitioner shall be allowed to have full movement access from the proposed entrance onto Endhaven Lane as depicted on the Conceptual Site Plan and Technical Data Sheet.

B. Petitioner shall be allowed to have right in - right out access from the proposed entrance onto the proposed extension of North Community House Road to be located contiguous along the property's western frontage, as depicted on the Conceptual Site Plan and Technical Data Sheet.

C. Access to parking areas will be as generally depicted on the Conceptual Site Plan and Technical Data Sheet. The placements and configurations of vehicular access points are subject to minor modifications required to accommodate final site and construction plans and designs and to any adjustments required for approval by the Charlotte Department of Transportation ("CDOT"), including alterations to accommodate right of way needs and/or construction easements.

D. Petitioner agrees to dedicate 100 feet of Right of Way along the site's (Parcel ID #22322298) western property line for the construction of future extension of North Community House Road.

E. Petitioner agrees to dedicate additional right of way along the sites northern property line to allow for the construction of required improvements along the Endhaven Lane frontage. Petitioner agrees to construct a westbound left turn lane with up to 100' feet of stacking along Endhaven Lane to provide required full-movement vehicular access to the project's easternmost entrance.

3. Architectural Standards

A. Attached hereto are Conceptual Schematic Architectural Renderings of the front elevations of the multi-family residential apartment buildings proposed to be constructed on the site. These renderings are intended to depict the general conceptual architectural style, character and elements of these buildings. Modifications to the elevations will be per section 6.207 of the Zoning Ordinance.

B. Building Materials: Architectural Design Guidelines have been provided with this Rezoning Petition in order to define the Project's architectural character. The exterior elevations of all buildings constructed on the site will be constructed using the Design Guidelines, provided that a mixture of allowable exterior building materials listed below can change among individual buildings. The Design Guidelines provide examples of building design and includes allowable building materials, photographic examples of

allowable materials, and a series of conceptual vignettes. The conceptual vignettes (see page 7) are intended only to illustrate examples of a building facade that meets the criteria set forth in the Architectural Standards and is not a specific or binding building elevation, nor are they a full list of possibilities.

1. Allowable exterior building materials
a. Primary- External vertical elevations (exclusive of windows, doors and overhead entry doors) of all buildings shall be constructed with a minimum of 50% of the following materials:

- i. Brick
ii. Natural Stone (or synthetic equivalent)
iii. Architecturally-finished Precast Concrete
iv. Decorative/architecturally finished Concrete Masonry Units (CMU)

b. Secondary- External vertical elevations(Exclusive of windows, doors, and overhead entry doors) of all buildings shall be limited to a maximum of 50% of the following materials:

- i. Stucco
ii. Exterior Insulation & Finish Systems (EIFS)
iii. Pre-finished Architectural Metal Panel Systems
iv. Tile Cladding Systems (i.e. Porcelain, ceramic, Granite, etc.)
v. Cementitious board or siding

2. Prohibited exterior building materials
a. Vinyl Siding
b. Aluminum Horizontal Siding
c. Concrete Masonry Units (CMU) without architecturally or decorative finish, except for retaining walls.

C. Building Base: A recognizable base shall be provided. A building base shall be maintained through material transitions and building articulation. Building base materials shall include, but are not limited to the following:

- 1. Ledges, sills, trim or banding
2. Integrally textured, colored, or patterned materials such as stone or brick.

Base may be varied in height. A building base is not required at full height fenestrations (i.e. curtain wall system), and key entry elements.

D. Massing and Development Scale: Facades shall be designed to reduce the mass, scale and uniform monolithic appearance of large unadorned walls, while providing visual interest. Large building facades shall be divided into distinct massing elements utilizing methods including but not limited to facade offsets, pilasters or change in materials. A roof line more than 120 feet in length shall include a change in height. This change in height shall align with the vertical building bays.

- 1. Setbacks should vary along Community House Road to avoid a solid wall.
2. At least 70% of the ground floor facade along North Community House and Endhaven Lane will be articulated principally through the use of windows, doors, balconies and breezeways/pedestrian access corridors.
3. No spans of blank, unarticulated wall greater than 20' is permitted along North Community House Road or Endhaven Lane.
4. Building materials should vary from the base floor to upper stories.

E. Service Areas Screening: Building service areas (dumpsters, refuse areas and building loading docks) of all buildings will be screened from view with masonry walls. The walls will be a minimum of 5 feet in height and will be designed to match and complement the building architecture of the adjacent buildings. Architectural features such as, but not limited to, banding, medallions, changes in color or design features or materials will be provided to avoid a sterile, unarticulated blank treatment of such walls. Roof top HVAC and related mechanical equipment will be screened from public view at grade from the nearest public street.

4. Parking: The Petitioner proposes to provide a combination of surface parking throughout the site, along with underground parking within Building B. Parking proposed underneath Building B will not be visible from North Community House Road. Applicant may incorporate up to 12 one-car garages with individual garage doors on the ground level of building A. Access may only be from the internal parking area on the eastern side of Building A. Garages will not be oriented towards North Community House Road or Endhaven Lane.

5. Streetscape and Landscaping: Internal areas of the Site will be landscaped in accordance with requirements of the Ordinance. A six (6) foot wide public sidewalk, large maturing street trees (or small maturing trees 30' O.C. where utility wires exist) and an eight (8) foot wide planting strip area will be installed along North Community House Road/ Endhaven Lane frontages. The Petitioner will connect internal "private" sidewalks within the Site to the public sidewalk system along the future roadways in order to provide a pedestrian-friendly development.

- A. A minimum of five (5) foot wide sidewalk access, internal to the Site, shall be provided to each multi-family residential apartment building.
B. Utilities located within the Site, such as meter boxes and back flow preventors, will be screened from view from the public street.
C. All other screening and landscaping shall conform to the standards of the Ordinance.
D. Petitioner shall provide pedestrian connections to the east side of North Community House Road and the southern edge of Endhaven Lane as generally depicted on the Conceptual Site Plan.

6. Amenities:

A. Amenities shall include a swimming pool, an indoor Clubhouse facility (integrated into the first floor of the building), outdoor seating areas and landscaping. An outdoor Amenity Pool area shall be provided in the location generally shown on the Conceptual Site Plan. The Petitioner reserves the right to locate the indoor Clubhouse facility and Amenity Pool area in proximity of Building A or Building B.

B. Open Space Areas: Open Space areas have been provided as part of the project. These areas include conceptual hardscape components that have been labeled and annotated within plan details as follows:

Building A - an approximate 4225 square foot outdoor plaza area at the corner of North Community House Road and Endhaven Lane is being included to showcase the main building and create a sense of arrival for the project. This outdoor urban open space area includes a large decorative fountain with pedestrian scale site lighting, seating areas with possible umbrellas (seasonal), a low accent wall with potential signage, decorative walks with brick or stone pavement treatment, specialty hardscape components, various shrubs and canopy shade trees that transition into a lawn area along each project frontage.

Building B - an approximate 2782 square foot outdoor patio area with seating and other pedestrian related gathering areas with landscaping, shade trees, decorative walks with brick or stone pavement treatment, specialty hardscape components, a fabric canopy structure, and related lawn areas to promote and accommodate outdoor gatherings associated with the apartment community activities.

7. Environmental Features:

A. The petitioner shall comply with the Charlotte City Council approved and adopted Post Construction Controls Ordinance. The location, size, and type of stormwater management systems depicted on the Rezoning Plan are subject to review and approval as part of the full development plan submittal and are not implicitly approved with this rezoning. Adjustments may be necessary in order to accommodate actual storm water treatment requirements and natural site discharge points.

B. Stormwater facilities shown on the Conceptual Site Plan/Rezoning Plan are proposed to be underground, covered by Parking Area.

C. Wetlands delineation, as applicable to the property will be provided upon submission of construction drawings for development on the Site.

8. Signage: Signage shall comply with the requirements of the Ordinance.

9. Lighting:

A. The maximum height of any detached lighting fixtures erected on the Site shall not exceed twenty (20) feet in height.

B. All freestanding lighting fixtures installed within the Site shall be shielded with full cut-off fixtures, capped and downwardly directed. However, low-level decorative lighting may be installed along driveways and parking areas.

C. Any attached lighting will be full cutoff fixture, fully shielded, downwardly directed.

10. Cell Tower: Applicant proposes to relocate the existing cell tower from its current location to an area in proximity as shown on the Conceptual Site Plan. The final revised location shall comply with all requirements of Chapter 12 of the Zoning Ordinance. Cell Tower shall be screened with evergreen trees planted 4'-6' in height at a minimum of 12' on center.

11. Tree Save: Tree Save areas shall comply with the requirements of the Ordinance.

12. Amendments to Rezoning Plan: Future amendments to the Technical Data Sheet, other sheets accompanying the Petition and these Development Standards may be applied for by the then Owner or Owners of the Parcel or Parcels within the Site involved in accordance with the provisions of Chapter 6 of the Ordinance.

13. Vested Rights: Pursuant to GS 160A-385.1, North Carolina General Statutes and Section 1.110 of the Ordinance, the Petitioner requests 5 year vested rights as a result of the proposed development and market conditions.

14. Binding Effect of the Rezoning Documents and Definitions:

A. If this Rezoning Petition is approved, all conditions applicable to development of the Site imposed under these Development Standards and the Technical Data Sheet will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of the Petitioners and the current and subsequent owners of the Site and their respective successors in interest and assigns.

B. Throughout these Development Standards, the terms, "Petitioners" and "Owner" or "Owners" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of the Petitioners or the Owner or Owners of the Site from time to time who may be involved in any future development thereof.

C. Any reference to the Ordinance herein shall be deemed to refer to the requirements of the Ordinance in effect as of the date this Rezoning Petition is approved.



ESP Associates, P.A.

engineering • surveying • planning
P.O. Box 7030 Charlotte, NC 28241
3475 Lakemont Blvd. Fort Mill, SC 29708
P - 704.583.4949 F - 803.802.2440
F - 704.583.4950 F - 803.802.2515

www.espassociates.com

This drawing and/or the design shown are the property of ESP Associates, P.A. The reproduction, alteration, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action. ESP Associates, P.A.

CLIENT



Trotter Builders
1515 Mockingbird Lane, Suite 900
Charlotte, NC 28209

PROJECT

North Community House Residences

SHEET TITLE

Development Standards

Petition 2013-098 "For Public Hearing"

PROJECT LOCATION Charlotte, North Carolina

Table with columns: PROJECT NO, DRAWING, DATE, DRAWN BY, CHECKED BY, AGENCY / SUBMITTAL REVISION, NO., DATE, BY, REVISION. Row 1: 1, 12-20-13, GW, staff comments