



NOTES
SEE SHEET RZ3.0 FOR SITE DEVELOPMENT NOTES.



SITE SUMMARY	
TAX PARCEL NUMBER	167-172-05, 167-172-06, 167-172-07, & 167-172-10
SITE AREA	85.3 ACRES (84.316 ACRES EXCLUSIVE OF PROPOSED R/W)
EXISTING ZONING	0-1 (CD) & B-1 (CD) ¹
PROPOSED ZONING	0-1 (CD) & 0-1 (CD) SPA
PROPOSED DENSITY	660,881 SF TOTAL BUILDING AREA (EXISTING) 928,000 SF ALLOWABLE BUILDING AREA (CONDITIONAL ZONING LIMIT) 267,119 SF ALLOWABLE BUILDING AREA REMAINING (CONDITIONAL ZONING LIMIT) 528,000 SF ADDITIONAL BUILDING SPACE (PROPOSED) 1,188,881 SF TOTAL BUILDING AREA (PROPOSED)
PROPOSED BLDG. HEIGHT	78' HT. MAX.
PROPOSED USE	COMMERCIAL OFFICE
REQUIRED YARDS:	50'/40' SETBACKS 10' SIDE YARD 20' REAR YARD

ColeJenest & Stone

Shaping the Environment
Realizing the Possibilities

Land Planning
Landscape Architecture
Civil Engineering
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
p 704.376.1555 f 704.376.7851
url www.colejeneststone.com

DUDA PAINE ARCHITECTS

Time Warner Cable

7815 Crescent Executive Drive
Charlotte,
North Carolina 28217

TIME WARNER CABLE REZONING

Charlotte
North Carolina 28217

TECHNICAL DATA SHEET PET. # 2014-091

Project No.
4332

Issued
07/28/14

Revised

1 09/19/2014

2 10/24/2014




SCALE: 1"= 100'

RZ1.0

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A.. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.


ColeJenest & Stone, P.A. 2014 ©

PET. # 2014-091



VICINITY MAP N.T.S.

SURVEY DISCLAIMER
PORTION OF TOPOGRAPHIC AND EXISTING CONDITIONS SURVEY
INFORMATION PROVIDED BY ESP ASSOCIATES, P.A., PO BOX
7030, CHARLOTTE, NC 28241, (704) 585-4949, DATED
AUGUST 23, 2011.



Shaping the Environment
Realizing the Possibilities

Land Planning
Landscape Architecture
Civil Engineering
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
p 704 376 1555 f 704 376 7851
url www.colejeneststone.com



7815 Crescent Executive Drive
Charlotte,
North Carolina 28217

TIME WARNER CABLE REZONING


Charlotte
North Carolina 28217

CONCEPTUAL SITE PLAN PET. # 2014-091

Project No.
4332

Issued
07/28/14

Revised



RZ2.0

The drawings, the project manual and the design shown thereon
are instruments of ColeJenest & Stone, P.A.. The reproduction
or unauthorized use of the documents without consent of
ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2014 ©

PET. # 2014-091

DEVELOPMENT NOTES

SITE DEVELOPMENT DATA:

- ACREAGE: ± 85.3 ACRES
- TAX PARCEL #: 167-172-05, 167-172-06, 167-172-07, 167-172-10
- EXISTING ZONING: O-1 (CD) AND B-1 (CD)
- PROPOSED ZONING: O-1 (CD)
- EXISTING USES: OFFICE
- PROPOSED USES: OFFICE
- MAXIMUM BUILDING HEIGHT: 78'
- PARKING: PROVIDED PER SECTION 12.202 OF THE CITY OF CHARLOTTE ZONING ORDINANCE

1. GENERAL PROVISIONS:

- a. SITE LOCATION. THESE DEVELOPMENT STANDARDS FORM A PART OF THE REZONING PLAN ASSOCIATED WITH THE REZONING PETITION FILED BY TIME WARNER CABLE ("PETITIONER") TO ACCOMMODATE THE DEVELOPMENT OF AN OFFICE CAMPUS ON APPROXIMATELY 85.3 ACRE SITE LOCATED NORTH OF ARROWWOOD ROAD (THE "SITE").
- b. ZONING DISTRICTS/ORDINANCE. DEVELOPMENT OF THE SITE WILL BE GOVERNED BY THE REZONING PLAN AS WELL AS THE APPLICABLE PROVISIONS OF THE CITY OF CHARLOTTE ZONING ORDINANCE (THE "ORDINANCE"). UNLESS THE REZONING PLAN ESTABLISHES MORE STRINGENT STANDARDS THE REGULATIONS ESTABLISHED UNDER THE ORDINANCE FOR THE O-1 ZONING CLASSIFICATION SHALL GOVERN.
- c. GRAPHICS AND ALTERATIONS. THE SCHEMATIC DEPICTIONS OF THE USES, PARKING AREAS, SIDEWALKS, STRUCTURES AND BUILDINGS, DRIVEWAYS, AND OTHER DEVELOPMENT MATTERS AND SITE ELEMENTS (COLLECTIVELY THE "DEVELOPMENT/SITE ELEMENTS") SET FORTH ON THE REZONING PLAN SHOULD BE REVIEWED IN CONJUNCTION WITH THE PROVISIONS OF THESE DEVELOPMENT STANDARDS. THE LAYOUT, LOCATIONS, SIZES AND FORMULATIONS OF THE DEVELOPMENT/SITE ELEMENTS DEPICTED ON THE REZONING PLAN ARE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT/SITE ELEMENTS PROPOSED. CHANGES TO THE REZONING PLAN NOT ANTICIPATED BY THE REZONING PLAN WILL BE REVIEWED AND APPROVED AS ALLOWED BY SECTION 6.207 OF THE ORDINANCE.

2. PERMITTED USES & DEVELOPMENT AREA LIMITATION:

- a. THE SITE MAY BE DEVELOPED WITH UP TO 1,188,881 SQUARE FEET OF TOTAL OFFICE SQUARE FOOTAGE TOGETHER WITH ACCESSORY USES WHICH ARE PERMITTED OR UNDER PRESCRIBED CONDITIONS IN THE O-1 (CD) ZONING DISTRICT.
- b. THE SURFACE PARKING AREAS DEPICTED ON THE REZONING PLAN MAY VARY IN SIZE AND LOCATION. BUT IN ALL EVENTS WILL BE SUFFICIENT TO SATISFY THE MINIMUM OFF-STREET PARKING STANDARDS ESTABLISHED UNDER THE APPLICABLE ORDINANCES. PARKING AREAS MAY BE CONSTRUCTED WITHIN THE BUILDING LIMIT LINES.
- c. SQUARE FOOTAGE OF PARKING DECK STRUCTURES WILL NOT COUNT TOWARD THE TOTAL BUILD OUT SQUARE FOOTAGE FOR THE PROJECT, FOLLOWING ESTABLISHED PRECEDENT FOR THE CAMPUS.
- d. NUMBER OF BUILDINGS PRINCIPAL AND ACCESSORY. THE TOTAL NUMBER OF PRINCIPAL BUILDINGS TO BE DEVELOPED ON THE SITE SHALL NOT EXCEED TWELVE (12) WHICH INCLUDES EXISTING AND PROPOSED BUILDINGS AND PARKING DECKS. ACCESSORY BUILDINGS AND STRUCTURES LOCATED ON THE SITE SHALL NOT BE CONSIDERED IN ANY LIMITATION ON THE NUMBER OF BUILDINGS ON THE SITE. ACCESSORY BUILDINGS AND STRUCTURES WILL BE CONSTRUCTED UTILIZING SIMILAR BUILDING MATERIALS, COLORS, ARCHITECTURAL ELEMENTS AND DESIGNS AS THE PRINCIPAL BUILDING LOCATED ON THE SITE.
- e. PROJECT DEVELOPMENT AREA
 - i. THE PROJECT DEVELOPMENT AREA OF THE SITE MAY BE DEVOTED TO ANY USE (INCLUDING ANY ACCESSORY USE) WHICH IS PERMITTED BY RIGHT OR UNDER PRESCRIBED CONDITIONS IN AN O-1 ZONING DISTRICT.
 - ii. THE TOTAL GROSS FLOOR AREA WITHIN THE PROJECT DEVELOPMENT AREA OF THE SITE WHICH MAY BE DEVOTED TO OFFICE USES CANNOT EXCEED 1,188,881 SQUARE FEET.

3. ACCESS AND TRANSPORTATION:

- a. ACCESS TO THE SITE WILL BE FROM CRESCENT EXECUTIVE DRIVE AND GREEN RIDGE DRIVE IN THE MANNER GENERALLY DEPICTED ON THE REZONING PLAN.
- b. THE PLACEMENT AND CONFIGURATION OF THE VEHICULAR ACCESS POINTS ARE SUBJECT TO ANY MINOR MODIFICATIONS REQUIRED TO ACCOMMODATE FINAL SITE DEVELOPMENT AND CONSTRUCTION PLANS AND TO ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY CDOT IN ACCORDANCE WITH APPLICABLE PUBLISHED STANDARDS.
- c. THE ALIGNMENT OF THE INTERNAL VEHICULAR CIRCULATION AND DRIVEWAYS MAY BE MODIFIED BY THE PETITIONER TO ACCOMMODATE CHANGES IN TRAFFIC PATTERNS, PARKING LAYOUTS AND ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY CDOT IN ACCORDANCE WITH PUBLISHED STANDARDS.
- d. THE PETITIONER RESERVES THE RIGHT TO CONVERT A PORTION OF GREEN RIDGE ROAD SOUTH OF BUILDING 3 (EXISTING) AND THE FUTURE BUILDING ON THE SOUTH SIDE OF THE SITE TO A PRIVATE STREET TO ALLOW FOR A RAISED PEDESTRIAN CROSSING CONDITION WITH ALTERNATE PAVING MATERIALS (PAVERS).
- e. PER SECTION 12.206 OF THE CHARLOTTE ZONING ORDINANCE, SITE PLAN IS PERMITTED TO HAVE SEPARATION DISTANCES WHICH EXCEED 400 FEET, BUT ARE LESS THAN 1200 FEET BASED ON ESTABLISHED PRECEDENT FOR THE CAMPUS, AND THE FOLLOWING HEIGHTENED PEDESTRIAN AMENITIES:
 - 1. PEDESTRIAN LIGHTING. DEVELOPER WILL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH THE LIGHTING IF SUCH ITEMS ARE PLACED IN THE PUBLIC RIGHT-OF-WAY.
 - 2. A WELL-DEFINED PEDESTRIAN PATHWAY SYSTEM INCLUDING SIDEWALKS OF NO LESS THAN SIX-FEET IN WIDTH
 - 3. A CIRCULATORY BUS (SHUTTLE) SYSTEM THROUGHOUT THE SITE
- f. NOT USED.
- g. ADDITIONAL RIGHT OF WAY ALONG THE SOUTHERN MARGIN OF THE SITE WILL BE DEDICATED TO THE PUBLIC AUTHORITY HAVING JURISDICTION OVER ARROWWOOD ROAD IF ANY SUCH RIGHT OF WAY IS REQUIRED TO SATISFY THE COMMITMENTS MADE BY THE PETITIONER UNDER PARAGRAPH (3) (i).
- h. PETITIONER TO CONSTRUCT A WAITING PAD FOR THE EXISTING BUS STOP AT ARROWWOOD ROAD AND CRESCENT EXECUTIVE DRIVE. THE PAD IS TO BE CONSTRUCTED ACCORDING TO CLDS 60.01B AND WILL BE REVIEWED DURING THE PERMIT APPROVAL PROCESS.
- i. FUTURE IMPROVEMENTS TO EXISTING THROUGHFARES, SPECIFICALLY I-77 AND ARROWWOOD ROAD, ARE REQUIRED ONCE SPECIFIC THRESHOLDS RELATED TO TOTAL CONSTRUCTED BUILDING SQUARE FOOTAGES ARE MET OR EXCEEDED.
 - i.a. THE PETITIONER WILL CONSTRUCT A TEN (10) FOOT WIDE MULTI-USE SHARED PATH AND AN EIGHTEEN (18) FOOT WIDE PLANTING STRIP FROM CRESCENT EXECUTIVE DRIVE TO THE WESTERN MOST PROPERTY LINE. INSTALLATION OF THE PATH WILL OCCUR WHEN CONSTRUCTION OF THE ROAD AND DRIVEWAYS ARE DEDICATED ON THE TECHNICAL DATA SHEET WHICH IS WEST OF CRESCENT EXECUTIVE DRIVE AND ASSOCIATED WITH BUILDING A AND PARKING DECK A ON THE REZONING PLANS.
 - i.b. THE PETITIONER WILL EXTEND WESTBOUND DUAL LEFT-TURN TURN LANE STORAGE ON ARROWWOOD ROAD AT THE INTERSECTION OF ARROWWOOD ROAD AND SOUTH TRYON STREET FROM 220' TO APPROXIMATELY 345' EACH (WITHIN EXISTING MEDIAN).
 - i.c. PETITIONER TO EXTEND THE EXISTING DUAL RIGHT-TURN LANES TO A COMBINED 1,500' OR CONSTRUCT A THIRD RIGHT-TURN LANE ON SOUTHBOUND I-77 OFF-RAMP ONTO ARROWWOOD ROAD WITH A COMBINED TOTAL STORAGE OF APPROXIMATELY 1500', WHICHEVER OPTION IS AGREED TO BY BOTH NCDOT AND CDOT.
 - i.d. PETITIONER TO EXTEND EASTBOUND DUAL LEFT-TURN LANE STORAGE ON ARROWWOOD ROAD AT THE INTERSECTION OF ARROWWOOD ROAD AND CRESCENT EXECUTIVE DRIVE TO 310' AND 430' (WITHIN EXISTING MEDIAN).
- j. NOT USED.
- k. THE CONFIGURATIONS OF DRIVEWAYS AND ACCESS POINTS WITHIN THE SITE ARE SUBJECT TO MINOR SHIFTS OR OTHER MODIFICATIONS THAT MAY BE REQUIRED TO ACCOMMODATE FINAL SITE ENGINEERING AND CONSTRUCTION PLANS AND DESIGNS AND ARE FURTHER SUBJECT TO TRANSPORTATION AND THE CHARLOTTE DEPARTMENT OF TRANSPORTATION.
- l. SPECIAL EMPHASIS WILL BE GIVEN TO THE DESIGN AND CONSTRUCTION OF EACH ENTRANCE TO THE SITE. FEATURES WILL INCLUDE SUCH ELEMENTS AS LANDSCAPED MEDIANS AND COORDINATED SIGNAGE MONUMENTS.
- m. THERE SHALL BE NO VEHICULAR ACCESS BETWEEN TRACT I AND THE RESIDENTIAL ZONED PROPERTY LOCATED NW & W OF THE SITE.
- n. ADEQUATE SIGHT TRIANGLES MUST BE RESERVED AT THE EXISTING STREET ENTRANCES.
- o. ANY EXISTING/PROPOSED ACCESS LOCATION TO PUBLIC STREETS WILL REQUIRE DRIVEWAY PERMITS TO BE SUBMITTED TO CDOT FOR REVIEW AND APPROVAL. THE EXACT DRIVEWAY LOCATIONS AND TYPE/WIDTH OF THE DRIVEWAYS WILL BE DETERMINED BY CDOT DURING THE DRIVEWAY PERMIT PROCESS. THE LOCATION OF THE DRIVEWAY SHOWN ON THE SITE PLAN IS SUBJECT TO CHANGE IN ORDER TO ALIGN DRIVEWAYS ON THE OPPOSITE SIDE OF THE STREET AND COMPLY WITH CITY DRIVEWAY REGULATIONS AND THE CITY TREE ORDINANCE.
- p. ALL PROPOSED COMMERCIAL DRIVEWAY CONNECTIONS TO A FUTURE PUBLIC STREET WILL REQUIRE A DRIVEWAY PERMIT TO BE SUBMITTED TO CDOT FOR REVIEW AND APPROVAL.
- q. ANY FENCE OR WALL CONSTRUCTED ALONG OR ADJACENT TO ANY SIDEWALK OR STREET RIGHT-OF-WAY REQUIRES A CERTIFICATE ISSUED BY CDOT.
- r. A RIGHT-OF-WAY ENCROACHMENT AGREEMENT IS REQUIRED FOR THE INSTALLATION OF ANY NON-STANDARD ITEM(S) (IRRIGATION SYSTEMS, DECORATIVE CONCRETE PAVEMENT, BRICK PAVERS, ETC.) WITHIN A PROPOSED/EXISTING CITY MAINTAINED STREET RIGHT-OF-WAY BY A PRIVATE INDIVIDUAL, GROUP, BUSINESS, OR HOMEOWNER'S BUSINESS ASSOCIATION. AN ENCROACHMENT AGREEMENT MUST BE APPROVED BY CDOT PRIOR TO THE CONSTRUCTION/INSTALLATION OF THE NON-STANDARD ITEM(S). CONTACT CDOT FOR ADDITIONAL INFORMATION CONCERNING COST, SUBMITTAL, AND LIABILITY INSURANCE COVERAGE REQUIREMENTS.

4. ARCHITECTURAL STANDARDS:

- a. THE BUILDING MATERIALS USED ON THE PRINCIPAL BUILDINGS CONSTRUCTED ON SITE WILL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING: ALUMINUM PANELS AND SOFFITS, PAINTED ALUMINUM FINIS AND MULLIONS, LOW-E VISION GLASS WITH CERAMIC FRIT, SPANDREL GLASS IN VARIOUS COLORS, AND STONE PANELS IN ALUMINUM SUB-FRAME. PLEASE REFER TO EXISTING PRECEDENTS SHEET R25.0 FOR PRECEDENT.
- b. HVAC AND RELATED MECHANICAL EQUIPMENT WILL BE SCREENED FROM PUBLIC VIEW AND FROM VIEW OF

ADJACENT PROPERTIES AT GRADE.

- c. ALL TRASH AND UTILITY SERVICE AREAS WILL BE SCREENED.
- d. REFLECTIVE GLASS MAY NOT BE USED AS THE SOLE EXTERIOR ARCHITECTURAL ELEMENT OR DESIGN OF ANY BUILDING CONSTRUCTED WITHIN THE PROJECT.
- e. ALSO, NO BUILDING CONSTRUCTED WITHIN DEVELOPMENT AREAS SHALL EXCEED SIX STORIES IN HEIGHT AS MEASURED FROM THE HIGHEST EXISTING GROUND ELEVATION ALONG THE SITE'S WESTERLY PROPERTY LINE.
- f. THE PETITIONER INTENDS TO ACHIEVE COMPATIBILITY OF VISUAL AESTHETICS AND ARCHITECTURAL DESIGN OF BUILDING AND STRUCTURED PARKING (IF ANY) CONSTRUCTED WITHIN THE PROJECT DEVELOPMENT AREA THROUGH THE USE OF ONE OR A COMBINATION OF COLOR, MATERIAL, TEXTURE, ARCHITECTURAL FACADES, ROOFLINES, BUILDING MASSES, SCALE AND SIMILAR CRITERIA. PROVIDED, HOWEVER, THAT PETITIONER SHALL HAVE THE RIGHT TO UTILIZE VARIANT COLORS, MATERIALS, TEXTURES, ARCHITECTURAL FACADES, ROOFLINES, BUILDING MASSES AND SCALES AS LONG AS COMPATIBILITY IN AESTHETICS AND DESIGN IS ACHIEVED.
- g. THE GENERAL ARCHITECTURAL STYLE AND CONSTRUCTION MATERIALS USED IN THE DEVELOPMENT OF THE O-1 (CD) AREA OF THE SITE SHALL BE SUBSTANTIALLY SIMILAR IN QUALITY AND GENERAL IMPRESSION WITH THE FOLLOWING OFFICE PARKS WHICH ARE LOCATED NEAR THE SITE:

OAKHILL OFFICE PARK
FOREST BROOK OFFICE PARK
ARROWPOINT OFFICE PARK

- a. THE PETITIONER RESERVES THE RIGHT TO LOCATE THE SATELLITE DISH FARM WITHIN THE PROPOSED PARKING DECK ALONG ARROWWOOD ROAD WHERE EQUIPMENT WOULD BE LOCATED IN A SUNKEN WELL WITHIN THE DECK TO SCREEN IT FROM THE PUBLIC RIGHT OF WAY.
- b. NEW PARKING DECKS CONSTRUCTED AS PART OF THE PROJECT WILL BE DESIGNED TO COMPLEMENT THE OWNER'S EXISTING PARKING INITIATIVES INCLUDING PREFERRED PARKING FOR "CLEAN COMMUTERS" (CARPOOL AND VANPOOL SPACES) AS WELL AS POTENTIAL CONSIDERATION FOR HYBRID AND ELECTRICAL VEHICLE SPACES.

5. STREETSCAPE, BUFFERS, YARDS AND LANDSCAPING:

- a. NO BUILDING OR PARKING AREAS MAY BE PLACED WITHIN ANY BUFFER AREA ESTABLISHED ON THIS REZONING PLAN.
- b. THE EXISTING TREE COVER AND NATURAL VEGETATION WITHIN THE WESTERN BUFFER AREAS ADJACENT TO WOODRIDGE SUBDIVISION ESTABLISHED ON THE REZONING PLAN WILL BE PRESERVED. THE PETITIONER RESERVES THE RIGHT, HOWEVER, TO REMOVE VINES, UNDERBRUSH AND SMALL UNDERSTORY TREES FOR THE PURPOSE OF IMPROVING THE OVERALL APPEARANCES OF NATURALLY VEGETATED AREAS. IN ANY EVENT, ALL BUFFER AREAS SHALL BE ESTABLISHED AND MAINTAINED IN ACCORDANCE WITH ORDINANCE REQUIREMENTS.
- c. IN THE WESTERN BUFFER AREAS ADJACENT TO WOODRIDGE SUBDIVISION WHERE EXISTING TREES AND NATURAL VEGETATION HAVE BEEN CLEARED, ALL SUCH CLEARED, UNIMPROVED AREAS WILL BE LANDSCAPED IN ORDER TO ATTAIN THE DESIRED SCREENING RELATIONSHIPS BETWEEN THE SITE AND ADJOINING PROPERTIES EXCEPT IN AREAS WHERE THE APPLICABLE ORDINANCES OR CONSTRAINTS IMPOSED BY UTILITIES WOULD PROHIBIT SUCH LANDSCAPING.
- d. ALONG ARROWWOOD ROAD A 50 FOOT SETBACK AS MEASURED FROM THE RIGHT-OF-WAY WILL BE PROVIDED AS GENERALLY DEPICTED ON THE REZONING PLAN. NO BUILDINGS OR PARKING AREAS MAY BE LOCATED WITHIN THE 50 FOOT SETBACK AREA AS THE SAME MAY BE RELOCATED TO ACCOMMODATE THE TRANSPORTATION IMPROVEMENTS CONTEMPLATED UNDER THE PROVISIONS OF PARAGRAPH (i). THESE SETBACK AREAS WILL BE ATTRACTIVELY LANDSCAPED WITHIN THE BUFFER, INCLUDING LAWNS AND/OR NATURAL VEGETATION AND WILL BE A CONTINUATION OF THE DESIGN IMPLEMENTED ADJACENT TO THE DATA CENTER.
- e. ALONG CRESCENT EXECUTIVE DRIVE A 20 FOOT SETBACK AS MEASURED FROM THE RIGHT-OF-WAY WILL BE PROVIDED AS GENERALLY DEPICTED ON THE REZONING PLAN.
- f. ALONG GREEN RIDGE DRIVE A 40 FOOT SETBACK AS MEASURED FROM THE RIGHT-OF-WAY WILL BE PROVIDED AS GENERALLY DEPICTED ON THE REZONING PLAN.
- g. AN FOUR (4) FOOT PLANTING STRIP AND A FIVE (5) FOOT SIDEWALK WILL BE PROVIDED ALONG THE SITE'S FRONTAGE ON CRESCENT EXECUTIVE DRIVE AND GREEN RIDGE DRIVE.
- h. THE INTERIOR ROAD SYSTEM WHICH INCORPORATES INTERMITTENT 8 FOOT WIDE MEDIANS AND WHICH ARE LANDSCAPED SO AS TO REFLECT A PARKWAY/BOULEVARD ATMOSPHERE WILL BE PRESERVED. ADDITIONAL BREAKS/CUTS IN THE MEDIANS FOR VEHICULAR ACCESS OFF OF GREEN RIDGE DRIVE MAY BE INSTALLED.
- i. A 100 FOOT CLASS "B" BUFFER WILL BE PROVIDED WHERE THE SITE ABUTS EXISTING SINGLE-FAMILY HOMES AS GENERALLY DEPICTED ON THE REZONING PLAN.
- j. SCREENING REQUIREMENTS OF THE ORDINANCE WILL BE MET.
- k. ABOVE GROUND BACKFLOW PREVENTERS WILL BE SCREENED FROM PUBLIC VIEW AND WILL BE LOCATED OUTSIDE OF THE REQUIRED SETBACKS. ABOVE GROUND BACK FLOW PREVENTERS MAY BE LOCATED IN THE LAST TEN FEET OF THE 35 FOOT LANDSCAPE SETBACK (I.E. THE 10 FEET OF THE LANDSCAPE SETBACK CLOSEST TO THE PROPOSED BUILDINGS).
- l. DUMPSTER AREAS AND RECYCLING AREAS WILL BE ENCLOSED BY A SOLID WALL OR FENCE WITH ONE SIDE BEING A DECORATIVE GATE. THE WALL OR FENCE USED TO ENCLOSE THE DUMPSTER WILL BE ARCHITECTURALLY COMPATIBLE WITH THE BUILDING MATERIALS AND COLORS USED ON THE PRINCIPAL BUILDING. THE LOCATION OF THE PROPOSED DUMPSTER AND RECYCLING AREAS ARE GENERALLY DEPICTED ON THE REZONING PLAN. EXACT LOCATIONS TO BE DETERMINED DURING THE DESIGN DEVELOPMENT AND CONSTRUCTION PHASES.
- m. A CLASS "B" BUFFER WHICH CONTAINS A MINIMUM OF 100' IN DEPTH SHALL BE ESTABLISHED ALONG THE NORTHERLY EDGE OF THE SITE.
- n. NO BUILDINGS OR PARKING AREAS MAY BE CONSTRUCTED WITHIN THE AREA DEPICTED ON THE REZONING PLAN AS "OPEN SPACE".
- o. PROVISIONS WILL BE MADE FOR THE MAINTENANCE OF ALL BUFFER AREAS AND LANDSCAPED AREAS, EXCEPT THOSE AREAS WHICH ARE TO BE DEDICATED TO MECKLENBURG COUNTY FOR GREENWAY PURPOSES.
- p. A 75 FOOT CLASS "B" BUFFER IN ACCORDANCE WITH ORDINANCE STANDARDS SHALL BE ESTABLISHED ALONG THE WESTERLY EDGE OF THE SITE. FURTHERMORE, AN ADDITIONAL 25 FEET OF LAND AREA (NON-CLASS "B" BUFFER) SHALL ALSO BE MADE PART OF THE BUFFER, THUS MAKING FOR A 100 FOOT WIDE BUFFER AS NOTED ON THE SITE PLAN. ALL OR PORTIONS OF THIS 100' BUFFER MAY BE GRADED SO LONG AS THE PLANTING REQUIREMENTS OF THE 75' PORTION OF THE CLASS "B" BUFFER ARE MET. HOWEVER, AS NOTED ON THE PLAN, A FENCE, ERECTED IN ACCORDANCE WITH ORDINANCE STANDARDS, SHALL BE PROVIDED AT THE ENTRANCE AT HANSON ROAD WHERE INADEQUATE SPACE IS AVAILABLE TO COMPLY WITH THE 75 FOOT CLASS "B" BUFFER. THE FENCE SHALL BE LOCATED AT THE POINT NO CLOSER THAN 25 FEET FROM THE WESTERNLY PROPERTY LINE WITH THE POSSIBLE EXCEPTION OF A SMALL AREA AT THE INTERSECTION (ARROWWOOD RD/STREET ENTRANCE) WHERE THE FENCE MAY BE DESIGNED AS A SIGN IDENTIFICATION FEATURE OF THE OFFICE PARK.

6. LANDSCAPING AND SCREENING:

- a. ALL DUMPSTER AND SERVICE AREAS WILL BE HEAVILY SCREENED FROM PUBLIC STREETS AND FROM ADJACENT PROPERTIES.
- b. ALL OPEN (NON-STRUCTURED) PARKING LOTS WILL HAVE LANDSCAPING AND PLANTED AREAS EQUAL TO AT LEAST TO PAVED AREAS SO AS TO PREVENT MASSING OF PAVED SURFACES.
- c. THE LANDSCAPING PROGRAM FOR PARKING AREAS WILL SATISFY THE REQUIREMENTS OF THE APPLICABLE ORDINANCES.

7. ENVIRONMENTAL FEATURES:

- a. THE PETITIONER SHALL COMPLY WITH THE CHARLOTTE CITY COUNCIL APPROVED AND ADOPTED POST CONSTRUCTION CONTROLS ORDINANCE.
- b. STORM WATER RUNOFF FROM THE SITE WILL BE MANAGED THROUGH A VARIETY OF PROVEN TECHNIQUES WHICH SATISFY THE STANDARDS IMPOSED BY THE APPLICABLE ORDINANCES. IN NO EVENT, HOWEVER, SHALL ANY STORM WATER MANAGEMENT SYSTEM BE LOCATED IN A REQUIRED BUFFER.
- c. THE PROJECT WILL COMPLY WITH MECKLENBURG COUNTY AIR QUALITY REQUIREMENTS.
- d. THE LOCATION, SIZE AND TYPE OF STORM WATER MANAGEMENT SYSTEMS, INCLUDING EASEMENTS, DEPICTED ON THE REZONING PLAN ARE SUBJECT TO REVIEW AND APPROVAL AS PART OF THE FULL DEVELOPMENT PLAN SUBMITTAL AND ARE NOT IMPLICITLY APPROVED WITH THIS REZONING. ADJUSTMENTS MAY BE NECESSARY IN ORDER TO ACCOMMODATE ACTUAL STORM WATER TREATMENT REQUIREMENTS AND NATURAL SITE DISCHARGE POINTS.
- e. THE SITE WILL COMPLY WITH THE TREE ORDINANCE, INCLUDING TREE SAVE REQUIREMENTS.
- f. LANDSCAPING MUST CONFORM TO CITY OF CHARLOTTE REQUIREMENTS.

8. SIGNAGE:

- a. SIGNS WILL BE PROVIDED PER THE ORDINANCE.
- b. NO OUTDOOR BILLBOARDS MAY BE PLACED ON THE SITE.
- c. NOT USED.
- d. TEMPORARY PROJECT SIGNS MAY BE LOCATED WITHIN THE SETBACK OR BUFFER AREAS ESTABLISHED ALONG ARROWWOOD ROAD.

9. LIGHTING:

- a. A UNIFORM STREET LIGHTING SYSTEM WITH UNDERGROUND SERVICE WILL BE EMPLOYED THROUGHOUT THE AREA OF THE SITE.
- b. ALL DIRECT LIGHTING WILL BE DESIGNED SUCH THAT LIGHTING IS DIRECTED AWAY FROM ADJACENT RESIDENTIAL PROPERTIES.
- c. ALL PARKING DECK LIGHTING WILL BE 12' IN HEIGHT AND DESIGNED SUCH THAT LIGHTING IS DIRECTED AWAY FROM ADJACENT RESIDENTIAL PROPERTIES.
- d. DETACHED LIGHTING ON THE SITE WILL BE LIMITED TO 15 FEET IN HEIGHT.

10. FIRE PROTECTION

ADEQUATE FIRE PROTECTION IN THE FORM OF FIRE HYDRANTS WILL BE PROVIDED TO THE CITY OF CHARLOTTE

FIRE MARSHAL'S SPECIFICATIONS. PLANS FOR EACH BUILDING WILL BE SUBMITTED FOR APPROVAL BY THE FIRE MARSHAL'S OFFICE BEFORE CONSTRUCTION OF THE BUILDING COMMENCES.

11. GREENWAY DEDICATION





ALL OF THE LAND WITHIN THE SITE WHICH LIES WITHIN THE FLOODWAY ENCROACHMENT DISTRICT OF BIG SUGAR CREEK WILL BE DEDICATED TO MECKLENBURG COUNTY AS PART OF ITS GREENWAY PARK SYSTEM, SUBJECT ONLY TO THE PETITIONER'S RIGHT TO RETAIN MINOR PORTIONS THEREOF WHERE REQUIRED TO AVOID UNDEE IRREGULARITIES IN DIMENSIONS. A MINIMUM DEPTH OF 100' OF THE GREENWAY AREA, AS MEASURED FROM THE TOP OF THE CREEK BANK AND RUNNING PARALLEL TO THE CREEK BANK, SHALL BE DEDICATED AT THE TIME OF THE ISSUANCE OF THE FIRST BUILDING PERMIT ASSOCIATED WITH ANY DEVELOPMENT CONTAINED WITHIN THE PROJECT. THE BALANCE OF THE GREENWAY SHALL BE DEDICATED NO LATER THAN THE ISSUANCE OF THE LAST BUILDING PERMIT ASSOCIATED WITH THE DEVELOPMENT.

12. AMENDMENTS TO THE REZONING PLAN:

FUTURE AMENDMENTS TO THE REZONING PLAN (WHICH INCLUDES THESE DEVELOPMENT STANDARDS) MAY BE APPLIED FOR BY THE THEN OWNER OR OWNERS OF THE APPLICABLE DEVELOPMENT AREA PORTION OF THE SITE AFFECTED BY SUCH AMENDMENT IN ACCORDANCE WITH THE PROVISIONS OF CHAPTER 6 OF THE ORDINANCE.

13. BINDING EFFECT OF THE REZONING APPLICATION:


IF THIS REZONING PETITION IS APPROVED, ALL CONDITIONS APPLICABLE TO THE DEVELOPMENT OF THE SITE IMPOSED UNDER THE REZONING PLAN WILL, UNLESS AMENDED IN THE MANNER PROVIDED UNDER THE ORDINANCE, BE BINDING UPON AND INURE TO THE BENEFIT OF THE PETITIONER AND SUBSEQUENT OWNERS OF THE SITE AND THEIR RESPECTIVE HEIRS, DEVISEES, PERSONAL REPRESENTATIVES, SUCCESSORS IN INTEREST OR ASSIGNS.



ADJOINING PROPERTY OWNERS

(PETITON #'S 93-9 AND 87-9)

- 1. 167-168-30 DENNIS A. & JOAN D. BAXTER 7729 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 2. 167-168-29 ROBERT M. & DEBORAH A. GILLIAM 7719 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 3. 167-168-28 ROY & MARLENY CRISANTO 7713 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 4. 167-168-27 NAKISHA BOSAH & CHRISTOPHER FINLEY 7707 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 5. 167-168-26 BROADWAY WENDELL WILKIE 7701 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 6. 167-168-25 JOSEPH W. DIXON 7649 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 7. 167-168-24 VANESSA G. LUSTER 7643 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 8. 167-168-23 NADIA BOULIL 7637 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 9. 167-168-22 JEROME & ROBIN W. STRAYHORN 7633 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 10. 167-168-21 WILLIE J. MOBLEY & SHARON MOORE 7626 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 11. 167-168-20 GABRIEL ASSOMANI & PAULA TATE 7619 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 12. 167-168-19 TEDDY K. & GERGINA B. AGYEMANG 7613 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 13. 167-168-18 DORIS A. FOOTE 7607 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 14. 167-168-17 BRYANT L. PARHAM 7549 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 15. 167-168-16 SHAQUANNA POTTS 7543 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 16. 167-168-15 ROBERTO E. MENDOZA & ALBA LUIZ RIGUEZ MORALES 7537 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 17. 167-168-14 LATONYA S. ROSE 7531 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 18. 167-168-13 LISA PFALTZRAF 7527 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 19. 167-168-12 EDWIN CAMPOS 7523 WOODKNOLL DRIVE CHARLOTTE, N.C. 28217
- 20. 167-211-26 ROY LEE LOWERY, JR. 7526 BRADGATE ROAD CHARLOTTE, N.C. 28210
- 21. 167-213-01 HUONG T. HA 7525 BRADGATE ROAD CHARLOTTE, N.C. 28210
- 22. 167-213-09 DOUGLAS G. AND SHANNON M. LEE 7516 MANFORD COURT CHARLOTTE, N.C. 28210
- 23. 167-213-10 JANICE W. & OTTO BLAKE JR. 7515 MANFORD COURT CHARLOTTE, N.C. 28210
- 24. 167-213-15 EDDIE L. AND MARY P. WEATHERS 1515 RANCHWOOD DRIVE CHARLOTTE, N.C. 28210
- 25. 167-214-01 AUDREY F. HILL 1520 RANCHWOOD COURT CHARLOTTE, N.C. 28210
- 26. 167-214-04 JESSIE R. JORDAN 1609 OLD TOWNE COURT CHARLOTTE, N.C. 28210
- 27. 167-214-10 MECKLENBURG COUNTY 600 E. FOURTH STREET CHARLOTTE, N.C. 28202
- 28. 167-172-03 RAY B. SHRUM 651 SANDRIDGE ROAD CHARLOTTE, N.C. 28210
- 29. 167-172-11 MECKLENBURG COUNTY 600 E. FOURTH STREET CHARLOTTE, N.C. 28202



Shaping the Environment
Realizing the Possibilities

Land Planning
Landscape Architecture
Civil Engineering
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
P# 704.376.1555 F# 704.376.7851
W# www.colejeneststone.com



7815 Crescent Executive Drive
Charlotte,
North Carolina 28217

TIME WARNER
CABLE
REZONING

Charlotte
North Carolina 28217

DEVELOPMENT
NOTES

PET. # 2014-091

Project No.

4332

Issued

07/28/14

Revised

09/19/2014
10/24/2014




RZ3.0

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2014 ©

PET. # 2014-091



VICINITY MAP

N.T.S.

SURVEY DISCLAIMER
PORTION OF TOPOGRAPHIC AND EXISTING CONDITIONS SURVEY INFORMATION PROVIDED BY ESP ASSOCIATES, P.A., PO BOX 7030, CHARLOTTE, NC 28241, (704) 585-4949, DATED AUGUST 23, 2011.

ColeJenest & Stone
DUDA PAINE ARCHITECTS

Shaping the Environment
Realizing the Possibilities

Land Planning
+
Landscape Architecture
+
Civil Engineering
+
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
p+ 704.376.1555 f+ 704.376.7851
url+ www.colejeneststone.com

Time Warner Cable®

7815 Crescent Executive Drive
Charlotte,
North Carolina 28217

**TIME WARNER
CABLE
REZONING**



Charlotte
North Carolina 28217

04

RZ4.0

Site Section through Future Parking Deck B

Scale: 1" = 50'-0"




03

RZ4.0

Site Section through Future Buildings 4-6 and Parking Deck A

Scale: 1" = 50'-0"




02

RZ4.0

Site Section through Future Parking Deck A

Scale: 1" = 50'-0"



01

RZ4.0

Site Section through Future Building 4

Scale: 1" = 50'-0"

**SITE CROSS
SECTIONS**

PET. # 2014-091

Project No.
4332

Issued
07/28/14

Revised

09/19/2014
10/24/2014



RZ4.0

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A.. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2014 ©

PET. # 2014-091




107 - EXISTING TIME WARNER CABLE CAMPUS LOOKING NORTH EAST
SCALE: N/A



DENSE LANDSCAPING
BUFFER BETWEEN
GARAGE AND
ADJACENT
RESIDENTIAL
SUBDIVISION

LUSH GARDENS
AND WATER
FEATURES
SURROUNDED BY
WALKING PATHS




SEATING AREAS IN
GARDENS

COVERED WALKWAYS

PATHWAY LIGHTING



108 - EXISTING TIME WARNER CABLE CAMPUS DESIGN ELEMENTS
SCALE: N/A





ColeJenest & Stone
DUDA PAINE ARCHITECTS

*Shaping the Environment
Realizing the Possibilities*

Land Planning
+
Landscape Architecture
+
Civil Engineering
+
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
p+ 704.376.1555 f+ 704.376.7851
url+ www.colejeneststone.com



7815 Crescent Executive Drive
Charlotte,
North Carolina 28217

TIME WARNER CABLE REZONING

Charlotte
North Carolina 28217

EXISTING PRECEDENTS PET. # 2014-091

Project No.
4332

Issued
07/28/14

Revised
09/19/2014
10/24/2014



ALUMINUM PANELS
AND SOFFITS


PAINTED ALUMINUM
FINS AND
MULLIONS

LOW-E VISION
GLASS WITH
CERAMIC FRIT

LOW-E VISION
GLASS

SPANDREL GLASS
IN THREE SHADES
OF BLUE

STONE PANELS IN
ALUMINUM
SUB-FRAME



104 - EXISTING BUILDING FINISH MATERIALS
SCALE: N/A



ARCHITECTURAL
LIGHTING

ARCHITECTURAL
PRECAST CONCRETE
GARAGE WITH
SPANDREL PANELS
AND REVEAL
PATTERNS ON ALL
FOUR SIDES

ALUMINUM PANELS

PAINTED ALUMINUM
FINS AND
MULLIONS

SPANDREL GLASS
IN THREE SHADES
OF BLUE

EVERGREEN
LANDSCAPING
BUFFER

PAINTED
GUARDRAILS


LANDSCAPING
BUFFER OF
EVERGREENS AND
DECIDUOUS TREES

PERIMETER FENCE
FOR DATA CENTER
SECURITY

105 - EXISTING DATA CENTER FINISH MATERIALS
SCALE: N/A



106 - EXISTING GARAGE FINISH MATERIALS
SCALE: N/A



102 - PROPOSED CAMPUS ELEVATION ALONG ARROWOOD ROAD
SCALE: N/A



ROOFTOP
EQUIPMENT IS
SCREENED FROM
VIEW

COVERED WALKWAYS

COVERED ENTRY

101 - EXISTING CAMPUS ELEVATION ALONG GREEN RIDGE DRIVE
SCALE: N/A



RZ5.0

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A.. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2014 ©

PET. # 2014-091