

SITE DEVELOPMENT DATA:
 ACREAGE: ±3.3 ACRES
 TAX PARCEL #: 08304711, 08304710, 08304701, 08304702, 08304712.
 EXISTING ZONING: I-2
 PROPOSED ZONING: TOD-M(CD)
 EXISTING USES: INDUSTRIAL
 PROPOSED USES: UP TO 280 MULTI-FAMILY DWELLING UNITS TOGETHER WITH ACCESSORY USES, AS ALLOWED IN THE ZONING DISTRICT.
 PROPOSED FLOOR AREA RATIO: AS ALLOWED BY THE ZONING DISTRICT.
 MAXIMUM BUILDING HEIGHT: 120'
 PARKING: PARKING AS REQUIRED BY THE ORDINANCE WILL BE PROVIDED.

1. General Provisions:
 a. Site Location. These Development Standards form a part of the Rezoning Plan associated with the Rezoning Petition filed by Wood Partners. ("Petitioner") to accommodate the development of a 280 unit multi-family community on approximately 3.3 acre site located at the intersection of North Brevard and East 25th Street.
 b. Zoning Districts/Ordinance. Development of the Site will be governed by the Rezoning Plan as well as the applicable provisions of the City of Charlotte Zoning Ordinance (the "Ordinance"). Unless the Rezoning Plan establishes more stringent standards the regulations established under the Ordinance for the TOD-M(CD) zoning classification shall govern.
 c. Graphics and Alterations. The schematic depictions of the uses, parking areas, sidewalks, structures and buildings, building elevations, driveways, streets and other development matters and site elements (collectively the "Development/Site Elements") set forth on the Rezoning Plan should be reviewed in conjunction with the provisions of these Development Standards. The layout, locations, sizes and formulations of the Development/Site Elements depicted on the Rezoning Plan are graphic representations of the Development/Site elements proposed. Changes to the Rezoning Plan not anticipated by the Rezoning Plan will be reviewed and approved as allowed by Section 6.207 of the Ordinance.
 Since the project has not undergone the design development and construction phases, it is intended that this Rezoning Plan provide for flexibility in allowing some alterations or modifications from the graphic representations of the Development/Site Elements. Therefore, there may be instances where minor modifications will be allowed without requiring the Administrative Amendment Process per Section 6.207 of the Ordinance.

2. Permitted Uses & Development Area Limitation:
 b. The Site may be developed with up to 280 multi-family dwelling units together with accessory structures.
3. Access and Transportation:
 a. Access to the Site will be from East 24th Street in the manner generally depicted on the Rezoning Plan. East 24th Street to be constructed to Local Residential Wide Standards. The placement and configuration of the access points are subject to any minor modifications required by the Charlotte Department of Transportation (CDOT) but no additional driveways will be created on any street other than E 24th Street.
 b. The alignment of the internal circulation, circulation of the parking garage and driveways may be modified by the Petitioner to accommodate changes in traffic patterns, parking layouts and any adjustments required for approval by CDOT.


4. Streetscape/Landscaping/Buffers/Open Space
 a. The Site will comply with the TOD-M(CD) standards with respect to the streetscape along the site's frontage on public streets.
 b. The Site will comply with the applicable landscaping, screening and buffer requirements of the ordinance.
5. Architectural Standards, Court Yards/Amenity Areas:
 a. The building materials used on the principal buildings constructed on Site will be a combination of portions of some or all of the following: brick, stone, precast stone, precast concrete, synthetic stone, cementitious fiber board, stucco, EIFS, Trepa, decorative block and/or wood. Vinyl or aluminum as a building material may only be used on windows, soffits and on handrails/railings.
 b. Building facade facing the Cross Charlotte Trail will not have a blank wall of more than 20' vertically or horizontally on any floor.
 c. HVAC and related mechanical equipment will be screened from public view and from view of adjacent properties at grade.

6. Environmental Features:
 a. The Petitioner shall comply with the Charlotte City Council approved and adopted Post Construction Controls Ordinance.
 b. The Site will comply with the Tree Ordinance.
 c. Trees greater than two (2) inches in diameter as measured 4.5' above ground and in the street right of way are protected by law; authorization for their removal is to be coordinated through the City Arborist office.
 d. The stream will be delineated during site plan development.

7. Parks, Greenways and Open Space
 a. The petitioner will initiate the procedure to dedicate & convey, to the County Parks and Recreation the SWM Buffer along Little Sugar Creek. This area will be conveyed to the County Parks and Recreation Department prior to the issuance of a certificate of occupancy for the first unit.
 b. Pedestrian scaled lighting will be provided on the project connection to the Cross Charlotte Trail.
 c. Transitions between the proposed development and Cross Charlotte Trail may include landscaping, paving, stoops, street trees, benches and pedestrian lighting.
 d. Building design facing the Cross Charlotte Trail will incorporate taller ground floor and facade articulation. Building facade facing the Cross Charlotte Trail will not have a blank wall of more than 20' vertically or horizontally on any floor.
 e. Above ground utilities and service areas will not be located adjacent to the trail.

8. Fire Protection
 a. Reserved
9. Signage:
 a. Signage as allowed by the Ordinance will be provided.
10. Lighting:
 a. All new lighting shall be full cut-off type lighting fixtures excluding lower, decorative lighting that may be installed along the driveways, sidewalks, parking areas and courtyards.
 b. Detached lighting on the Site will be limited to 20 feet in height.
11. Phasing:
 a. Reserved
12. Amendments to the Rezoning Plan:
 a. Future amendments to the Rezoning Plan (which includes these Development Standards) may be applied for by the Current Applicant or Successors with the consent of the Owner of the applicable Development Area portion of the Site affected by such amendment in accordance with the provisions of Chapter 6 of the Ordinance.

13. Binding Effect of the Rezoning Application:
 a. If this Rezoning Petition is approved, all conditions applicable to the development of the Site imposed under the Rezoning Plan will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of the Petitioner and subsequent owners of the Site and their respective heirs, devisees, personal representatives, successors in interest or assigns.




VICINITY MAP (NTS)



- landscape architecture
- civil engineering
- urban design
- land planning
- traffic engineering
- transportation planning

2459 wilkinson boulevard, suite 200
 charlotte, nc 28208
 p 704.343.0608 f 704.358.3093
 www.drgrp.com



NODA LOFTS AT 25TH AND BREVARD
 CHARLOTTE, NORTH CAROLINA

WP EAST ACQUISITIONS
 1001 MOREHEAD SQUARE DRIVE, SUITE 250
 CHARLOTTE, NC 28203
 704.332.8995

REZONING PETITION

FOR PUBLIC HEARING
 2016-005

SCALE: 1" = 30'

PROJECT #: 041-194
 DRAWN BY: KC
 CHECKED BY: SC

SCHEMATIC SITE PLAN

SEPTEMBER 28, 2015

REVISIONS:
 1. 12-18-15 - PER STAFF COMMENTS