

ROAD LEGEND

	PRIVATE STREET
	PUBLIC STREET
	ACCESS POINT
(\mathbf{R})	RIGHT IN/RIGHT
FM	FULL MOVEMENT
HOO TO T	SIGNALIZED INT

SITE DEVELOPMENT NOTES:

-ACREAGE: +/- 77.31 ACRES -TAX PARCEL #'S: 105-361-01, 105-361-05, 105-361-06 -EXISTING ZONING: R-8MF (CD), R-12MF (CD), O-2 (CD), AND NO ZONING (ON FORMER I-485 R/W) -PROPOSED ZONING: CC -EXISTING USES: VACANT -PROPOSED USES: USES PERMITTED BY RIGHT AND UNDER PRESCRIBED CONDITIONS TOGETHER WITH ACCESSORY USES, AS ALLOWED IN THE CC ZONING DISTRICT (AS MORE SPECIFICALLY DESCRIBED IN SECTION 2 ON SHEET RZ-2). -MAXIMUM GROSS SQUARE FT OF DEVELOPMENT: UP TO 191,000 SQUARE FEET OF GROSS FLOOR AREA OF NON-RESIDENTIAL USES AS ALLOWED IN THE CC ZONING DISTRICT, INCLUDING A MOTION PICTURE THEATER, PLUS A HOTEL WITH UP TO 120 ROOMS, AND UP TO 515 RESIDENTIAL DWELLING UNITS, TOGETHER WITH ACCESSORY USES AS ALLOWED BY THE CC ZONING DISTRICT.

-MAXIMUM BUILDING HEIGHT: AS ALLOWED BY THE ORDINANCE. -PARKING: AS REQUIRED BY THE ORDINANCE WILL BE PROVIDED. PARKING FOR THE USES LOCATED WITHIN MECKLENBURG COUNTY MAY BE LOCATED ON THE PORTION OF THE SITE LOCATED WITHIN HARRISBURG AND VICE A VERSA.

PARCEL 'A' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF PROPOSED ZONING: CC PROPOSED USES: -residential

PARCEL 'B' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF PROPOSED ZONING: CC PROPOSED USES: -residential (townhomes)


PARCEL 'C' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF PROPOSED ZONING: CC PROPOSED USES: -residential

PARCEL 'D' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF / R-12MF PROPOSED ZONING: CC PROPOSED USES: -residential

PARCEL 'E' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF / R-12MF / O-2 PROPOSED ZONING: CC PROPOSED USES: -MIXED-USE

PARCEL 'F' COUNTY: MECKLENBURG EXISTING ZONING: R-8MF / R-12MF PROPOSED ZONING: CC PROPOSED USES: -MIXED USE


PARCEL 'G' COUNTY: MECKLENBURG EXISTING ZONING: R-12MF PROPOSED ZONING: CC PROPOSED USES: -NON-RESIDENTIAL



VICINITY MAP

NOTE: STREET CROSS-SECTIONS FOUND ON SHEET RZ-3.

NOTE: SEE CROSS-SECTIONS FOR SETBACK INFORMATION.



ROCKY RIVER ROAD ASSOCIATES, LLC DEVELOPMENT STANDARDS (04/10/17) REZONING PETITION NO. 2017-042

SITE DEVELOPMENT DATA:

--ACREAGE: ± 77.31

--**TAX PARCEL #:** 105-361-01, 05 AND 06 --**EXISTING ZONING:** R-8MF(CD), R-12MF(CD), O-2(CD), AND NO ZONING (ON FORMER I-485 R/W).

--PROPOSED ZONING: CC --EXISTING USES: VACANT

--PROPOSED USES: USES PERMITTED BY RIGHT AND UNDER PRESCRIBED CONDITIONS TOGETHER WITH ACCESSORY USES, AS ALLOWED IN THE CC ZONING DISTRICT (AS MORE SPECIFICALLY DESCRIBED BELOW IN SECTION 2).
--MAXIMUM GROSS SQUARE FEET OF DEVELOPMENT: UP TO 191,000 SQUARE FEET OF GROSS FLOOR AREA OF NON-RESIDENTIAL USES AS ALLOWED IN THE CC ZONING DISTRICT, INCLUDING A MOTION PICTURE THEATER, PLUS A HOTEL WITH UP TO 120 ROOMS, AND UP TO 515 RESIDENTIAL DWELLING UNITS, TOGETHER WITH ACCESSORY USES AS ALLOWED BY THE CC ZONING DISTRICT.
--MAXIMUM BUILDING HEIGHT: AS ALLOWED BY THE ORDINANCE.

--**PARKING:** AS REQUIRED BY THE ORDINANCE WILL BE PROVIDED. PARKING FOR THE USES LOCATED WITHIN MECKLENBURG COUNTY MAY BE LOCATED ON THE PORTION OF THE SITE LOCATED WITHIN HARRISBURG AND VICE A VERSA.

I. <u>GENERAL PROVISIONS</u>:

A. THESE DEVELOPMENT STANDARDS FORM A PART OF THE REZONING PLAN ASSOCIATED WITH THE REZONING PETITION FILED BY ROCKY RIVER ROAD ASSOCIATES, LLC TO ACCOMMODATE DEVELOPMENT OF A RESIDENTIAL, RETAIL, EDEE (RESTAURANT), OFFICE, AND OTHER ALLOWED NON-RESIDENTIAL USES, AS A MIXED-USE COMMUNITY ON AN 77.31 ACRE SITE LOCATED ON ROCKY RIVER ROAD AND PROPOSED FARMINGTON RIDGE PARKWAY (FORMERLY PLAZA RD. EXTENSION) (THE "SITE").

B. DEVELOPMENT OF THE SITE WILL BE GOVERNED BY THE REZONING PLAN AS WELL AS THE APPLICABLE PROVISIONS OF THE CITY OF CHARLOTTE ZONING ORDINANCE (THE "ORDINANCE"). UNLESS THE REZONING PLAN ESTABLISHES MORE STRINGENT STANDARDS, THE REGULATIONS ESTABLISHED UNDER THE ORDINANCE FOR THE CC CLASSIFICATION FOR THE SITE SO DESIGNATED ON THE REZONING PLAN, SHALL GOVERN ALL DEVELOPMENT TAKING PLACE ON THE SITE.

C. **GRAPHICS AND ALTERATIONS**. THE SCHEMATIC DEPICTIONS OF THE USES, PARKING AREAS, SIDEWALKS, STRUCTURES AND BUILDINGS, DRIVEWAYS, STREETS AND OTHER DEVELOPMENT MATTERS AND SITE ELEMENTS (COLLECTIVELY THE "DEVELOPMENT/SITE ELEMENTS") SET FORTH ON THE REZONING PLAN SHOULD BE REVIEWED IN CONJUNCTION WITH THE PROVISIONS OF THESE DEVELOPMENT STANDARDS. THE LAYOUT, LOCATIONS, SIZES AND FORMULATIONS OF THE DEVELOPMENT/SITE ELEMENTS DEPICTED ON THE REZONING PLAN ARE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT/SITE ELEMENTS PROPOSED. CHANGES TO THE REZONING PLAN NOT ANTICIPATED BY THE REZONING PLAN WILL BE REVIEWED AND APPROVED AS ALLOWED BY SECTION 6.207 OF THE ORDINANCE.

SINCE THE PROJECT HAS NOT UNDERGONE THE DESIGN DEVELOPMENT AND CONSTRUCTION PHASES, IT IS INTENDED THAT THIS REZONING PLAN PROVIDE FOR FLEXIBILITY IN ALLOWING SOME ALTERATIONS OR MODIFICATIONS FROM THE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT/SITE ELEMENTS. THEREFORE, THERE MAY BE INSTANCES WHERE MINOR MODIFICATIONS WILL BE ALLOWED WITHOUT REQUIRING THE ADMINISTRATIVE AMENDMENT PROCESS PER SECTION 6.207 OF THE ORDINANCE. THESE INSTANCES WOULD INCLUDE CHANGES TO GRAPHICS IF THEY ARE: I. MINOR AND DON'T MATERIALLY CHANGE THE OVERALL DESIGN INTENT DEPICTED ON THE REZONING PLAN.

THE PLANNING DIRECTOR WILL DETERMINE IF SUCH MINOR MODIFICATIONS ARE ALLOWED PER THIS AMENDED PROCESS, AND IF IT IS DETERMINED THAT THE ALTERATION DOES NOT MEET THE CRITERIA DESCRIBED ABOVE, THE PETITIONER SHALL THEN FOLLOW THE ADMINISTRATIVE AMENDMENT PROCESS PER SECTION 6.207 OF THE ORDINANCE; IN EACH INSTANCE, HOWEVER, SUBJECT TO THE PETITIONER'S APPEAL RIGHTS SET FORTH IN THE ORDINANCE. D. **EXCLUSIONS FOR CALCULATION OF MAXIMUM DEVELOPMENT LEVELS**. FOR PURPOSES OF THE DEVELOPMENT LIMITATIONS SET FORTH IN THESE DEVELOPMENT STANDARDS (BUT NOT TO BE CONSTRUED AS A LIMITATION ON FAR REQUIREMENTS), THE FOLLOWING ITEMS WILL NOT BE COUNTED AS PART OF THE ALLOWED GROSS FLOOR AREA (AS DEFINED BY THE ORDINANCE) FOR THE SITE: SURFACE OR STRUCTURED PARKING FACILITIES, ALL LOADING DOCK AREAS (OPEN OR ENCLOSED), OPEN UNCONDITIONED SECOND STORY BALCONIES, AND OUTDOOR DINING AREAS WHETHER ON THE ROOF OF THE BUILDING(S) OR AT STREET LEVEL (PARKING FOR OUTDOOR DINING AREAS WILL BE PROVIDED AS REQUIRED BY THE ORDINANCE OR THESE DEVELOPMENT STANDARDS).

2. <u>PERMITTED USES & DEVELOPMENT AREA LIMITATION</u>:

A. SUBJECT TO THE RESTRICTIONS AND LIMITATIONS LISTED BELOW, THE PRINCIPAL BUILDINGS CONSTRUCTED ON THE SITE MAY BE DEVELOPED WITH UP TO 191,000 SQUARE FEET OF GROSS FLOOR AREA OF NON-RESIDENTIAL USES PERMITTED BY RIGHT AND UNDER PRESCRIBED CONDITIONS, INCLUDING A MOTION PICTURE THEATER, RETAIL, EDEE (RESTAURANTS), OFFICE USES, PLUS A HOTEL WITH 120 ROOMS, AND UP TO 515 RESIDENTIAL UNITS TOGETHER WITH ACCESSORY USES IN THE COMMERCIAL CENTER (CC) ZONING DISTRICT, AS APPLICABLE.

B. FOR EASE OF REFERENCE, THE REZONING PLAN SETS FORTH SEVEN (7) DEVELOPMENT AREAS AS GENERALLY DEPICTED ON THE TECHNICAL DATA SHEET AS DEVELOPMENT AREAS A, B, C, D, E, F AND G (EACH A "DEVELOPMENT AREA" AND COLLECTIVELY THE "DEVELOPMENT AREAS").

C. NONE OF THE PROPOSED BUILDINGS MAY BE CONSTRUCTED SO THAT THEY STRADDLE THE EXISTING COUNTY LINE. THE PROPOSED BUILDINGS MUST BE WHOLLY CONSTRUCTED WITHIN EITHER MECKLENBURG COUNTY OR CABARRUS COUNTY. PARKING FOR THE PROPOSED USES MAY BE LOCATED IN EITHER COUNTY.

D. WITHIN DEVELOPMENT AREAS A AND B UP TO 240 TOWNHOME FOR SALE (ONE-FAMILY ATTACHED DWELLING UNITS) WILL BE ALLOWED, AS ALLOWED IN THE CC ZONING DISTRICT TOGETHER WITH ACCESSORY USES AS ALLOWED BY THE CC ZONING DISTRICT. THE RESIDENTIAL DENSITY OF DEVELOPMENT AREAS A AND B IN THE AGGREGATE WILL NOT EXCEED EIGHT (8) DWELLING UNITS TO THE ACRE.

E. WITHIN DEVELOPMENT AREAS C, D, E, F AND G UP TO 275 RESIDENTIAL DWELLING UNITS, 191,000 SQUARE FEET OF GROSS FLOOR AREA OF NON-RESIDENTIAL USES, INCLUDING A MOTION PICTURE THEATER, PLUS A HOTEL WITH UP TO 120 ROOMS WILL BE ALLOWED, AS ALLOWED IN THE CC ZONING DISTRICT TOGETHER WITH ACCESSORY USES AS ALLOWED IN THE CC ZONING DISTRICT.

F. THE FOLLOWING USES WILL NOT BE ALLOWED ON THE SITE; CONVENIENCE STORES WITH OR WITHOUT FUEL SALES, AND EDEE (RESTAURANTS) WITH ACCESSORY DRIVE-THROUGH WINDOWS.

G. NO BUILDING PERMITS MAY BE ISSUED FOR THE DEVELOPMENT ALLOWED ON THE SITE UNTIL THE SITE HAS BEEN ANNEXED INTO THE CITY OF CHARLOTTE.

A. ACCESS TO THE SITE WILL BE FROM FARMINGTON RIDGE PARKWAY (THE EXTENSION OF PLAZA ROAD IN HARRISBURG). OLIVIA CATHERINE WAY WILL BE EXTENDED INTO THE SITE AS REQUIRED AND AT THE TIME IT IS REQUIRED TO BE EXTENDED BY THE SUBDIVISION REGULATIONS.

B. A NEW NETWORK OF PUBLIC AND PRIVATE STREETS WILL BE CONSTRUCTED ON SITE AS GENERALLY DEPICTED ON THE REZONING PLAN. A CROSS-SECTIONS FOR EACH OF THE PROPOSED STREETS HAS BEEN INCLUDED WITH THE PETITION. THE PROPOSED CROSS-SECTIONS INDICATE SETBACKS AS WILL STREETSCAPE ELEMENTS. THESE PROPOSED PUBLIC STREETS WILL BE CONSTRUCTED PER CITY OF CHARLOTTE DEVELOPMENT STANDARDS EVEN IF THE SITE IS NOT ANNEXED INTO THE CITY OF CHARLOTTE PRIOR TO THE CONSTRUCTION OF THE ROADS. THE PETITIONER HAS APPLIED FOR VOLUNTARY ANNEXATION OF THE SITE INTO THE CITY OF CHARLOTTE.

C. PER THE PREVIOUSLY APPROVED CONDITIONAL PLAN FOR THE SITE, AND DUE TO ENVIRONMENTAL ISSUES ASSOCIATED WITH THE EXTENSION OF BRANDON TRAIL DRIVE WILL NOT BE REQUIRED INTO THE SITE.

D. THE NUMBER AND LOCATION OF ACCESS POINTS TO THE INTERNAL PUBLIC AND PRIVATE STREETS WILL BE DETERMINED DURING THE LAND DEVELOPMENT APPROVAL PROCESS.

E. THE ALIGNMENT OF THE INTERNAL PUBLIC AND PRIVATE STREETS, VEHICULAR CIRCULATION AND DRIVEWAYS MAY BE MODIFIED BY THE PETITIONER TO ACCOMMODATE CHANGES IN TRAFFIC PATTERNS, PARKING LAYOUTS AND ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY THE CHARLOTTE DEPARTMENT OF TRANSPORTATION (CDOT) IN ACCORDANCE WITH PUBLISHED STANDARDS.

TRANSPORTATION IMPROVEMENTS

ACCESS AND PROPOSED ROADWAYS:

3.

THE PETITIONER PLANS TO PROVIDE OR CAUSE TO BE PROVIDED ON ITS OWN OR IN COOPERATION WITH OTHER PARTIES WHO MAY IMPLEMENT PORTIONS OF THE IMPROVEMENTS, THE IMPROVEMENTS SET FORTH BELOW TO BENEFIT OVERALL TRAFFIC PATTERNS THROUGHOUT THE AREA IN ACCORDANCE WITH THE FOLLOWING IMPLEMENTATION PROVISIONS:

THE FOLLOWING TRANSPORTATION IMPROVEMENTS ARE ALSO ILLUSTRATED ON FIGURE --10 LOCATED ON SHEET --RZ-2 OF THE REZONING PLAN. FIGURE --10 ON SHEET --RZ-2 IS TO BE USED IN CONJUNCTION WITH THE FOLLOWING NOTES TO DETERMINE THE EXTENT OF THE PROPOSED IMPROVEMENTS (REFERENCE TO A NUMBER WHEN DESCRIBING AN IMPROVEMENT CORRESPONDS TO THE NUMBER FOUND ON FIGURE --10 ON SHEET --RZ-2 FOR THE PROPOSED IMPROVEMENT).

THE FOLLOWING ROADWAY IMPROVEMENTS WILL BE MADE BY THE PETITIONER AS PART OF THE DEVELOPMENT OF THE SITE AS PROPOSED BY THE REZONING PLAN. THE PETITIONER WILL BE ALLOWED TO OBTAIN A CERTIFICATE OF OCCUPANCY FOR ANY ONE OR ALL OF THE BUILDINGS LOCATED ON THE SITE UPON THE SUBSTANTIAL COMPLETION OF THE FOLLOWING IMPROVEMENTS:

PROPOSED IMPROVEMENTS:

A. THE PETITIONER WILL EXTEND AND HAVE OPEN TO THE PUBLIC FARMINGTON RIDGE PARKWAY FROM ROCKY RIVER ROAD TO CALDWELL ROAD PRIOR TO THE ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY.

B. THE PETITIONER WILL STUDY AND CORRECT A POTENTIAL INTERSECTION SIGHT DISTANCE ISSUES AT FARMINGTON RIDGE PARKWAY AND CALDWELL ROAD (LOOKING WEST). IF A SIGHT DISTANCE ISSUE EXISTS AND IS NOT CORRECTED BY OTHERS THE PETITIONER WILL WORK WITH CDOT AND NCDOT TO CORRECT THE PROBLEM PRIOR TO THE ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY ON THE SITE.

C. I-485 INNER RAMP @ ROCKY RIVER ROAD: - PROVIDE SECOND EASTBOUND THROUGH LANE WITH 500 FEET OF STORAGE LENGTH AND APPROPRIATE TAPER - PROVIDE PROTECTED PERMITTED PHASING FOR WESTBOUND LEFT TURN TRAFFIC ALONG ROCKY RIVER ROAD (IN CONJUNCTION WITH HOLCOMBE'S

IMPROVEMENTS TO ROCKY RIVER ROAD & I-485).

D. ROCKY RIVER ROAD @ PLAZA ROAD EXTENSION/FARMINGTON RIDGE PARKWAY:

- CONSTRUCT DUAL EASTBOUND LEFT TURN LANES ALONG ROCKY RIVER ROAD WITH 325 FEET OF STORAGE AND APPROPRIATE TAPER. - MODIFY GEOMETRY OF THE NORTHBOUND APPROACH ALONG PLAZA ROAD EXTENSION TO PROVIDE DUAL NORTHBOUND LEFT TURN LANES (1 WITH 275

FEET OF STORAGE, 1 WITH FULL STORAGE), ONE THRU LANE (200 FEET OF STORAGE), AND ONE RIGHT TURN LANE (200 FEET OF STORAGE). - CONSTRUCT THE SOUTHBOUND APPROACH ALONG FARMINGTON RIDGE PARKWAY TO PROVIDE DUAL SOUTHBOUND LANES LEFT TURN LANES (200 FEET OF STORAGE), ONE THRU LANE, AND ONE RIGHT TURN LANE.

CONSTRUCT A WESTBOUND RIGHT TURN LANE ALONG ROCKY RIVER ROAD WITH 250 FEET OF STORAGE AND APPROPRIATE TAPER.
EXTEND THE EXISTING WESTBOUND LEFT TURN LANE ALONG ROCKY RIVER ROAD TO PROVIDE 300 FEET OF STORAGE AND APPROPRIATE TAPER.
MODIFY SIGNAL DESIGN ACCORDINGLY DUE TO GEOMETRIC IMPROVEMENTS.


E. ROCKY RIVER ROAD @ PROPOSED RIGHT-IN/RIGHT-OUT ACCESS:

- CONSTRUCT A WESTBOUND RIGHT TURN LANE ALONG ROCKY RIVER ROAD WITH 100 FEET OF STORAGE AND APPROPRIATE TAPER.


F. CALDWELL ROAD @ FARMINGTON RIDGE PARKWAY: - CONSTRUCT AN EASTBOUND RIGHT TURN LANE ALONG CALDWELL ROAD WITH 100 FEET OF STORAGE AND APPROPRIATE TAPER.


~~~~	IMP PLA SUF	D NC ROV CE \ POF	<b>DOT/NCDOT STANDARDS.</b> ALL OF THE FOREGOING PUBLIC ROADWAY IMPROVEMENTS WILL BE SUBJECT TO THE STANDARDS AND CRITERIA OF CDOT CDOT, AS APPLICABLE, TO THE ROADWAY IMPROVEMENTS WITHIN THEIR RESPECTIVE ROAD SYSTEM AUTHORITY. IT IS UNDERSTOOD THAT SUCH EMENTS MAY BE UNDERTAKEN BY THE PETITIONER ON ITS OWN OR IN CONJUNCTION WITH OTHER DEVELOPMENT OR ROADWAY PROJECTS TAKING WITHIN THE BROADER NORTHEAST MECKLENBURG AREA, BY WAY OF A PRIVATE/PUBLIC PARTNERSHIP EFFORT OR OTHER PUBLIC SECTOR PROJECT RT.]
	HO\ THA PHA APF	ALL I VEV AT TI ASINO PLICA CE A	JBSTANTIAL COMPLETION. REFERENCE TO "SUBSTANTIAL COMPLETION" FOR CERTAIN IMPROVEMENTS AS SET FORTH IN THE PROVISIONS ABOVE MEAN COMPLETION OF THE ROADWAY IMPROVEMENTS IN ACCORDANCE WITH THE STANDARDS SET FORTH IN SECTION 4.I.AB ABOVE PROVIDED, ER, IN THE EVENT CERTAIN NON-ESSENTIAL ROADWAY IMPROVEMENTS (AS REASONABLY DETERMINED BY CDOT) ARE NOT COMPLETED AT THE TIME HE PETITIONER SEEKS TO OBTAIN A CERTIFICATE OF OCCUPANCY FOR BUILDING(S) ON THE SITE IN CONNECTION WITH RELATED DEVELOPMENT G DESCRIBED ABOVE, THEN CDOT WILL INSTRUCT APPLICABLE AUTHORITIES TO ALLOW THE ISSUANCE OF CERTIFICATES OF OCCUPANCY FOR THE ABLE BUILDINGS, AND IN SUCH EVENT THE PETITIONER MAY BE ASKED TO POST A LETTER OF CREDIT OR A BOND FOR ANY IMPROVEMENTS NOT IN AT THE TIME SUCH A CERTIFICATE OF OCCUPANCY IS ISSUED TO SECURE COMPLETION OF THE APPLICABLE IMPROVEMENTS.
	OF CON AGE REII CON PRC	f be a 60 mme SNC` Mbu Mpei Dcee	<b>GHT-OF-WAY AVAILABILITY.</b> IT IS UNDERSTOOD THAT SOME OF THE PUBLIC ROADWAY IMPROVEMENTS REFERENCED IN SUBSECTION A. ABOVE MAY POSSIBLE WITHOUT THE ACQUISITION OF ADDITIONAL RIGHT OF WAY. IF AFTER THE EXERCISE OF DILIGENT GOOD FAITH EFFORTS OVER A MINIMUM DAY PERIOD, THE PETITIONER IS UNABLE TO ACQUIRE ANY LAND NECESSARY TO PROVIDE FOR ANY SUCH ADDITIONAL RIGHT OF WAY UPON RCIALLY REASONABLE TERMS AND AT MARKET PRICES, THEN CDOT, THE CITY OF CHARLOTTE ENGINEERING DIVISION OR OTHER APPLICABLE (, DEPARTMENT OR GOVERNMENTAL BODY AGREE TO PROCEED WITH ACQUISITION OF ANY SUCH LAND. IN SUCH EVENT, THE PETITIONER SHALL RSE THE APPLICABLE AGENCY, DEPARTMENT OR GOVERNMENTAL BODY FOR THE COST OF ANY SUCH ACQUISITION PROCEEDINGS INCLUDING NSATION PAID BY THE APPLICABLE AGENCY, DEPARTMENT OR GOVERNMENTAL BODY FOR ANY SUCH LAND AND THE EXPENSES OF SUCH EDINGS. FURTHERMORE, IN THE EVENT PUBLIC ROADWAY IMPROVEMENTS REFERENCED IN SUBSECTION A. ABOVE ARE DELAYED BECAUSE OF IN THE ACQUISITION OF ADDITIONAL RIGHT-OF-WAY AS CONTEMPLATED HEREIN AND SUCH DELAY EXTENDS BEYOND THE TIME THAT THE
······	Pet Des Occ Apf Imp	TTIO CRI CUP/ PLIC/ ROV	NER SEEKS TO OBTAIN A CERTIFICATE OF OCCUPANCY FOR BUILDING(S) ON THE SITE IN CONNECTION WITH RELATED DEVELOPMENT PHASING BED ABOVE, THEN THE PETITIONER WILL WORK WITH CITY STAFF TO DETERMINE A PROCESS TO ALLOW THE ISSUANCE OF CERTIFICATES OF ANCY FOR THE APPLICABLE BUILDINGS; PROVIDED, HOWEVER, PETITIONER CONTINUES TO EXERCISE GOOD FAITH EFFORTS TO COMPLETE THE ABLE ROAD-WAY IMPROVEMENTS; IN SUCH EVENT THE PETITIONER MAY BE ASKED TO POST A LETTER OF CREDIT OR A BOND FOR ANY EMENTS NOT IN PLACE AT THE TIME SUCH A CERTIFICATE OF OCCUPANCY IS ISSUED TO SECURE COMPLETION OF THE APPLICABLE IMPROVEMENTS.
·	DIR	AINIS ECT MPAI	LTERNATIVE IMPROVEMENTS. CHANGES TO THE ABOVE REFERENCED ROADWAY IMPROVEMENTS CAN BE APPROVED THROUGH THE STRATIVE AMENDMENT PROCESS UPON THE DETERMINATION AND MUTUAL AGREEMENT OF PETITIONER, CDOT AND NCDOT, AND THE PLANNING OR AS APPLICABLE, PROVIDED, HOWEVER, THE PROPOSED ALTERNATE TRANSPORTATION IMPROVEMENTS PROVIDE (IN THE AGGREGATE) RABLE TRANSPORTATION NETWORK BENEFITS TO THE IMPROVEMENTS IDENTIFIED IN THIS PETITION. GHT-OF-WAY DEDICATION. THE RIGHT-OF-WAY FOR THE NEW PUBLIC STREETS LOCATED ON THE PORTION OF THE SITE LOCATED IN MECKLENBURG
	COL EAS	JNT SEME HIND	( WILL BE OFFERED FOR DEDICATION AS REQUIRED BY THE SUBDIVISION REGULATIONS. A TWO (2) FOOT UTILITY AND STREET MAINTENANCE ENT WILL BE PROVIDED ALONG THE PROPOSED PUBLIC STREETS. THE TWO (2) FOOT UTILITY AND STREET MAINTENANCE EASEMENT WILL LOCATED THE PROPOSED SIDEWALK WHEN LESS THAN TWO (2) FEET OR RIGHT-OF-WAY WILL EXIST BEHIND THE PROPOSED SIDEWALK. CHITECTURAL STANDARDS:
		MBIN YL A	HE PRINCIPAL BUILDINGS CONSTRUCTED ON THE SITE MAY USE A VARIETY OF BUILDING MATERIALS. THE BUILDING MATERIALS USED WILL BE A IATION OF THE FOLLOWING: BRICK, STONE, SIMULATED STONE, PRE-CAST STONE, PRECAST CONCRETE, SYNTHETIC STONE, STUCCO, EIFS OR WOOD. S A BUILDING MATERIAL MAY ONLY BE USED ON WINDOWS, SOFFITS AND ON HANDRAILS/RAILINGS. RCHITECTURAL AND DESIGN CONTROLS
$\Sigma$	1.	N	DN-RESIDENTIAL BUILDING PLACEMENT AND SITE DESIGN SHALL FOCUS ON AND ENHANCE THE PEDESTRIAN ENVIRONMENT ON PUBLIC OR PRIVATE RK REQUIRED STREETS, THROUGH THE FOLLOWING:
		i.	BUILDINGS LOCATED ALONG THE PROPOSED "MAIN STREET" SHALL BE PLACED SO AS TO PRESENT A FRONT OR SIDE FAÇADE TO THE PROPOSED MAIN STREET. BUILDINGS LOCATED ALONG THE OTHER PROPOSED PUBLIC OR PRIVATE STREETS WILL MEET THE OTHER APPLICABLE PROVISIONS OF THE REZONING PLAN AND THE ORDINANCE REGARDING BUILDING FACADES WHEN LOCATED ALONG A PROPOSED PUBLIC OR PRIVATE STREET.
		ii.	BUILDINGS FRONTING ON THE EXISTING AND PROPOSED PUBLIC AND PRIVATE STREETS (OTHER THAN I-485 AND ASSOCIATED ON RAMPS) WILL BE ARTICULATED SUCH THAT EXPANSES OF SOLID WALLS EXCEEDING 20 LINEAR FEET WILL BE AVOIDED WITH EITHER HORIZONTAL AND VERTICAL VARIATIONS IN WALL PLANES, MATERIALS AND/OR BUILDING COLOR. A BLANK WALL IS A FAÇADE THAT DOES NOT ADD TO THE CHARACTER OF THE STREETSCAPE AND DOES NOT CONTAIN TRANSPARENT WINDOWS OR DOOR OR SUFFICIENT ORNAMENTATION, DECORATION OR ARTICULATION. WHEN THIS APPROACH IS NOT FEASIBLE ARCHITECTURAL ELEMENTS MUST BE USED ON THE BUILDING FAÇADE AT STREET LEVEL. ELEMENTS MAY INCLUDE, BUT ARE NOT LIMITED TO: MOLDING; STRING COURSES; BELT COURSES; CHANGES IN MATERIAL OR COLOR; ARCHITECTURAL LIGHTING; WORKS OF ART; DISPLAY AREAS, PORCHES, OR STOOPS.
		iii.	BUILDING FACADES (BUT NOT THE FACADES OF THE PROPOSED MOTION PICTURE THEATER) FRONTING ON PUBLIC OR PRIVATE STREETS (OTHER THAN I-485 AND ASSOCIATED ON RAMPS) SHALL INCLUDE A MINIMUM OF 30% TRANSPARENT GLASS BETWEEN TWO FEET (2') AND EIGHT FEET (8) ON THE FIRST FLOOR. SHADOW BOXES OR WINDOW GRAPHICS MAY BE UTILIZED BEHIND TRANSPARENT GLASS TO SCREEN BATHROOMS, BACK OF HOUSE, KITCHENS, OR OTHER BUILDING ELEMENTS; SHADOW BOXES OR WINDOW GRAPHICS MAY NOT BE UTILIZED FOR MORE THAN 10% OF THE REQUIRED TRANSPARENCY REQUIREMENT.
		iv.	THE FIRST FLOOR BUILDING FACADES FRONTING ON THE PROPOSED "MAIN STREET" (THE PROPOSED THEATER AS ILLUSTRATED DOES NOT FRONT ON THE "MAIN STREET") SHALL INCLUDE A MINIMUM OF 60% TRANSPARENT GLASS BETWEEN TWO (2) FEET AND EIGHT (8) FEET. SHADOW BOXES OR WINDOW GRAPHICS MAY BE UTILIZED BEHIND TRANSPARENT GLASS TO SCREEN BATHROOMS, BACK OF HOUSE, KITCHENS, OR OTHER BUILDING ELEMENTS; SHADOW BOXES OR WINDOW GRAPHICS MAY NOT BE UTILIZED FOR MORE THAN 10% OF THE REQUIRED TRANSPARENCY REQUIREMENT.
		v.	ALL BUILDINGS MUST BE SITED MAINTAINING PEDESTRIAN INTERCONNECTIVITY BETWEEN BUILDINGS AND THROUGH PARKING AREAS. THIS WILL BE DONE BY PROVIDING A MINIMUM OF A SIX (6) FEET SIDEWALK BETWEEN BUILDINGS AND THROUGH PARKING AREAS (PEDESTRIAN WALKWAYS IN PARKING AREAS WILL BE STRIPED), AND CONNECTING EACH BUILDING TO THE SIDEWALK NETWORK THAT WILL BE PROVIDED THROUGHOUT THE SITE.
			DIRECT PEDESTRIAN CONNECTIONS, VIA A SIDEWALK, SHOULD BE PROVIDED BETWEEN STREET FACING DOORS, CORNER ENTRANCE FEATURES TO SIDEWALKS ON ADJACENT STREETS. NOT ALL STREET FACING DOORS NEED TO BE DESIGN AS CUSTOMER DOORS, UNLESS LOCATED ON THE "MAIN STREET".
			BUILDING ELEVATIONS (BUT NOT THE SERVICE SIDES OF BUILDINGS WHEN LOCATED ADJACENT TO THE PARKING AREAS) SHALL BE DESIGNED WITH VERTICAL BAYS OR ARTICULATED ARCHITECTURAL FEATURES WHICH SHALL INCLUDE A COMBINATION OF AT LEAST THREE OF THE FOLLOWING: A COMBINATION OF EXTERIOR WALL OFFSETS (PROJECTIONS AND RECESSES), COLUMNS, PILASTERS, CHANGE IN MATERIALS OR COLORS, AWNINGS, ARCADES, OR OTHER ARCHITECTURAL ELEMENTS.
		VIII.	ALL BUILDINGS LOCATED WITHIN THE SITE WILL BE ARCHITECTURALLY INTEGRATED TO COMPLEMENT ONE ANOTHER BY USING SIMILAR OR COMPATIBLE ARCHITECTURAL STYLES, BUILDING MATERIALS, LANDSCAPE ELEMENTS, PLANTS AND SIGNAGE TREATMENTS TO CREATE A UNIFIED AND COHESIVE DEVELOPMENT. IN ADDITION, BUILDINGS LOCATED ON THE SITE MUST BE DESIGNED USING A SIMILAR; (I) ARCHITECTURAL STYLE, (II) BUILDING MATERIALS, (III) COLORS AND (IV) SIGNAGE SO THAT DEVELOPMENT ON THESE PARCELS CREATES A COHESIVE WHOLE AND NOT A SERIES OF BUILDINGS WITH UNRELATED AND WHOLLY DISSIMILAR ARCHITECTURAL STYLES, BUILDING MATERIALS, COLORS AND SIGNAGE.
		ix.	BUILDINGS WILL BE A MINIMUM HEIGHT OF 22'.
		x.	THE SERVICE AREAS OF THE NON-RESIDENTIAL BUILDINGS CONSTRUCTED WITHIN DEVELOPMENT AREA E, F, AND G WILL BE SCREENED FROM THE ADJOINING STREETS WITH WALLS DESIGNED TO MATCH AND COMPLIMENT THE BUILDING ARCHITECTURE OF THE ADJACENT BUILDINGS. ARCHITECTURAL FEATURES SUCH AS, BUT NOT LIMITED TO, BANDING, MEDALLIONS, CHANGES IN COLOR OR DESIGN FEATURES OR MATERIALS WILL BE PROVIDED TO AVOID A STERILE, UNARTICULATED BLANK TREATMENT OF SUCH WALLS.
	2.		CHITECTURAL AND SITE DESIGN STANDARDS FOR MULTI-FAMILY DEVELOPMENTS NOT INCLUDING TOWNHOMES.
			STREET SHALL COMPRISE A MINIMUM OF 20% OF THAT BUILDING'S ENTIRE FAÇADE FACING SUCH NETWORK STREET USING BRICK, NATURAL STONE (OR ITS SYNTHETIC EQUIVALENT), STUCCO, OR OTHER MATERIAL APPROVED BY THE PLANNING DIRECTOR. PROHIBITED EXTERIOR BUILDING MATERIALS: VINYL SIDING (BUT NOT VINYL HAND RAILS, WINDOWS OR DOOR TRIM).
		b. iii. a.	CONCRETE MASONRY UNITS NOT ARCHITECTURALLY FINISHED. BUILDING PLACEMENT AND SITE DESIGN SHALL FOCUS ON AND ENHANCE THE PEDESTRIAN ENVIRONMENT THROUGH THE FOLLOWING: BUILDINGS SHALL BE PLACED SO AS TO PRESENT A FRONT OR SIDE FAÇADE TO ALL NETWORK REQUIRED STREETS (PUBLIC OR PRIVATE).
			BUILDINGS SHALL FRONT A MINIMUM OF 30% OF THE TOTAL NETWORK REQUIRED STREET FRONTAGE ON THE SITE (EXCLUSIVE OF DRIVEWAYS, PEDESTRIAN ACCESS, POINTS, ACCESSIBLE OPEN SPACE, TREE SAVE OR NATURAL AREAS, TREE REPLANTING AREAS AND STORM WATER FACILITIES). PARKING LOTS SHALL NOT BE LOCATED BETWEEN ANY BUILDING AND ANY NETWORK REQUIRED PUBLIC OR PRIVATE STREET.
			BUILDING MASSING AND HEIGHT SHALL BE DESIGNED TO BREAK UP LONG MONOLITHIC BUILDING FORMS AS FOLLOWS: BUILDINGS EXCEEDING 120 FEET IN LENGTH SHALL INCLUDE MODULATIONS OF THE BUILDING MASSING/FACADE PLANE (SUCH AS RECESSES, PROJECTIONS, AND ARCHITECTURAL DETAILS). MODULATIONS SHALL BE A MINIMUM OF 10 FEET WIDE AND SHALL PROJECT OR RECESS A MINIMUM OF 2 FEET EXTENDING THROUGH AT LEAST A FULL FLOOR.
		a.	ARCHITECTURAL ELEVATION DESIGN - ELEVATIONS SHALL BE DESIGNED TO CREATE VISUAL INTEREST AS FOLLOWS: BUILDING ELEVATIONS SHALL BE DESIGNED WITH VERTICAL BAYS OR ARTICULATED ARCHITECTURAL FAÇADE FEATURES WHICH MAY INCLUDE BUT NOT BE LIMITED TO A COMBINATION OF EXTERIOR WALL OFFSETS, PROJECTIONS, RECESSES, PILASTERS, BANDING AND CHANGE IN MATERIALS OR COLORS. BUILDINGS SHALL BE DESIGNED WITH A RECOGNIZABLE ARCHITECTURAL BASE ON ALL FACADES FACING NETWORK REQUIRED PUBLIC OR PRIVATE
			STREETS. SUCH BASE MAY BE EXECUTED THROUGH USE OF PREFERRED EXTERIOR BUILDING MATERIALS (AS DEFINED ABOVE) OR ARTICULATED ARCHITECTURAL FAÇADE FEATURES AND COLOR CHANGES. BUILDING ELEVATIONS FACING NETWORK REQUIRED PUBLIC OR PRIVATE STREETS SHALL NOT HAVE EXPANSES OF BLANK WALLS GREATER THAN 20 FEET IN ALL DIRECTIONS AND ARCHITECTURAL FEATURES SUCH AS BUT TO LIMITED TO BANDING, MEDALLIONS OR DESIGN FEATURES OR MATERIALS WILL BE PROVIDED TO AVOID A STERILE, UNARTICULATED BLANK TREATMENT OF SUCH WALLS.
			ROOF FORM AND ARTICULATION - ROOF FORM AND LINES SHALL BE DESIGNED TO AVOID THE APPEARANCE OF A LARGE MONOLITHIC ROOF STRUCTURE AS FOLLOWS: LONG PITCHED OR FLAT ROOF LINES SHALL AVOID CONTINUOUS EXPANSES WITHOUT VARIATION BY INCLUDING CHANGES IN HEIGHT AND/OR ROOF
		C.	FORM, TO INCLUDE BUT NOT BE LIMITED TO GABLES, HIPS, DORMERS OR PARAPETS. FOR PITCHED ROOFS THE MINIMUM ALLOWED IS 4:12 EXCLUDING BUILDINGS WITH A FLAT ROOF AND PARAPET WALLS. ROOF TOP HVAC AND RELATED MECHANICAL EQUIPMENT WILL BE SCREENED FROM PUBLIC VIEW AT GRADE FROM THE NEAREST STREET. SERVICE AREA SCREENING - SERVICE AREAS SUCH AS DUMPSTERS, REFUSE AREAS, RECYCLING AND STORAGE SHALL BE SCREENED FROM VIEW
		vii.	WITH MATERIALS AND DESIGN TO BE COMPATIBLE WITH PRINCIPAL STRUCTURES. SUCH DESIGN SHALL INCLUDE A MINIMUM 20 PERCENT PREFERRED EXTERIOR BUILDING MATERIALS OR A CLASS B BUFFER NOT LESS THAN 10' IN DEPTH AT ALL ABOVE GRADE PERIMETER NOT PAVED FOR ACCESS.


~	viii.	RESIDENTIAL GROUND FLOOR ENTRANCES, RAISED A MINIMUM OF 12-24", WITH STOOPS SHALL BE PROVIDED ALONG THE PUBLIC STREETS WHEN PROPOSED RESIDENTIAL UNITS ARE LOCATED ON A PUBLIC STREET
	A	RCHITECTURAL AND SITE DESIGN STANDARDS FOR TOWNHOMES STYLE RESIDENTIAL DWELLINGS UNITS.
	i.	TO PROVIDE PRIVACY, ALL RESIDENTIAL ENTRANCES WITHIN 15 FEET OF THE SIDEWALK MUST BE RAISED FROM THE AVERAGE SIDEWALK GRADE A MINIMUM OF 12 INCHES.
	ii.	PITCHED ROOFS, IF PROVIDED, SHALL BE SYMMETRICALLY SLOPED NO LESS THAN 5:12, EXCEPT THAT ROOFS FOR PORCHES AND ATTACHED SHEDS MAY BE NO LESS THAN 2:12, UNLESS A FLAT ROOF ARCHITECTURAL STYLE IS EMPLOYED.
	iii.	USABLE PORCHES AND STOOPS SHALL FORM A PREDOMINANT FEATURE OF THE BUILDING DESIGN AND BE LOCATED ON THE FRONT AND/OR SIDE OF THE BUILDING. USABLE FRONT PORCHES SHOULD BE COVERED AND BE AT LEAST 6 FEET DEEP. STOOPS AND ENTRY-LEVEL PORCHES MAY BE COVERED BUT SHOULD NOT BE ENCLOSED.
	iv.	USABLE PORCHES AND STOOPS SHALL FORM A PREDOMINANT FEATURE OF THE BUILDING DESIGN AND BE LOCATED ON THE FRONT AND/OR SIDE OF THE BUILDING. USABLE FRONT PORCHES SHOULD BE COVERED AND BE AT LEAST 6 FEET DEEP. STOOPS AND ENTRY-LEVEL PORCHES MAY BE COVERED BUT SHOULD NOT BE ENCLOSED.
	V.	GARAGE DOORS VISIBLE FROM PUBLIC OR PRIVATE STREETS SHOULD MINIMIZE THE VISUAL IMPACT BY PROVIDING A SETBACK OF 12 TO 24 INCHES FROM THE FRONT WALL PLANE AND ADDITIONAL ARCHITECTURAL TREATMENTS SUCH AS TRANSLUCENT WINDOWS OR PROJECTING ELEMENTS OVER THE GARAGE DOOR OPENING.
	vi.	WALKWAYS SHOULD BE PROVIDED TO CONNECT ALL RESIDENTIAL ENTRANCES TO SIDEWALKS ALONG PUBLIC AND PRIVATE STREETS.
	vii.	TOWNHOUSE BUILDINGS SHOULD BE LIMITED TO 5 INDIVIDUAL UNITS OR FEWER. THE NUMBER OF INDIVIDUAL UNITS PER BUILDING WILL VARY WHEN POSSIBLE IN ADJACENT BUILDINGS TO HELP CREATE A VARIED STREETSCAPE.
	viii.	PREFERRED EXTERIOR BUILDING MATERIALS: ALL PRINCIPAL AND ACCESSORY BUILDINGS ABUTTING A NETWORK REQUIRED PUBLIC OR PRIVATE STREET SHALL COMPRISE A MINIMUM OF 20% OF THAT BUILDING'S ENTIRE FAÇADE FACING SUCH NETWORK STREET USING BRICK, NATURAL STONE (OR ITS SYNTHETIC EQUIVALENT), STUCCO, OR OTHER MATERIAL APPROVED BY THE PLANNING DIRECTOR.
	ix. a. b.	PROHIBITED EXTERIOR BUILDING MATERIALS: VINYL SIDING (BUT NOT VINYL HAND RAILS, WINDOWS OR DOOR TRIM). CONCRETE MASONRY UNITS NOT ARCHITECTURALLY FINISHED.
	C.	THE PETITIONER WILL COORDINATE THE GENERAL APPEARANCE OF THE SITE'S RESIDENTIAL AND NON-RESIDENTIAL BUILDINGS ARCHITECTURE, LANDSCAPING, SIGNAGE AND STREETSCAPE ELEMENTS BY UTILIZING GENERALLY SIMILAR BUILDING MATERIALS, COLORS, ARCHITECTURAL DETAILS, STREETSCAPES, LANDSCAPE MATERIALS AND LANDSCAPE DESIGNS.
	d.	RETAINING WALLS LOCATED ON THE SITE WILL BE TREATED WITH LANDSCAPING TO HELP SOFTEN THEIR APPEARANCE.
_	e.	ROOF TOP HVAC AND RELATED MECHANICAL EQUIPMENT WILL BE SCREENED FROM PUBLIC VIEW AT GRADE.
۲ ۲	A A TITIC OSS	I-485 WILL BE LANDSCAPED WITH TREES, SHRUBS AND OTHER LANDSCAPE MATERIALS, THE ARRANGEMENT AND PLACEMENT OF THE PROPOSED CAPING WILL BE DETERMINED BY THE PETITIONER DURING THE LAND DEVELOPMENT APPROVAL PROCESS. SETBACK AS REQUIRED BY THE CC ZONING DISTRICT WILL BE ESTABLISHED ALONG THE PROPOSED PUBLIC STREETS, PROVIDED, HOWEVER, THE ONER RESERVES THE RIGHT TO THE REDUCE THE CC DISTRICT SETBACK FROM 35 FEET TO 16 FEET AS ALLOWED BY THE ORDINANCE. THE ATTACHED -SECTIONS INCLUDE INFORMATION ON WHEN A REDUCED SETBACK AS ALLOWED BY THE ORDINANCE IS CONTEMPLATED. THE SETBACK ALONG THE SED PRIVATE STREETS WILL BE A MINIMUM OF 16 FEET AS MEASURED FROM THE PROPOSED BACK OF CURB.
~	s	URFACED PARKING SPACES WILL NOT BE LOCATED BETWEEN THE PROPOSED BUILDINGS AND THE NEW PUBLIC STREETS AND EXISTING ROCKY ROAD. THIS STANDARD WILL NOT APPLY TO I-485 AND IT ASSOCIATED ON-RAMP.
	REET	HE PETITIONER WILL PROVIDE EIGHT (8) FOOT PLANTING STRIPS AND EIGHT (8) FOOT SIDEWALKS ALONG THE SITE'S INTERNAL PUBLIC AND PRIVATE IS AS GENERALLY DEPICTED ON THE ATTACHED CROSS-SECTIONS. PLANTING STRIPS AND SIDEWALKS ALONG THE SITE'S OTHER PUBLIC AND E STREETS WILL BE INSTALLED TO THE EXTENT REQUIRED BY THE DESIGN STANDARDS FOR STREETS OUTLINED IN THE SUBDIVISION REGULATIONS.
	LIN	HE PETITIONER WILL PROVIDE A SIDEWALK AND A CROSS-WALK NETWORK THAT LINKS ALL THE BUILDINGS ON THE SITE WITH ONE ANOTHER BY WAY (S TO SIDEWALKS ALONG THE ABUTTING PUBLIC AND PRIVATE STREETS AND/OR OTHER PEDESTRIAN FEATURES. THE MINIMUM WIDTH FOR THESE (AL SIDEWALKS WILL BE SIX (6) FEET.
~	T	HE PROPOSED SIDEWALKS MAY MEANDER TO PRESERVE HEALTHY, LARGE, EXISTING TREES LOCATED WITHIN THE SETBACKS ALONG THE EXISTING STREETS.
	<u>E</u>	NVIRONMENTAL FEATURES:
	Т	HE PETITIONER SHALL COMPLY WITH THE CHARLOTTE CITY COUNCIL APPROVED AND ADOPTED POST CONSTRUCTION CONTROLS ORDINANCE.
	Т	HE SITE WILL COMPLY WITH THE TREE ORDINANCE.
	S	IGNAGE:
	R	ESERVED.
	L	IGHTING:
16		LL NEW LIGHTING SHALL BE FULL CUT-OFF TYPE LIGHTING FIXTURES EXCLUDING LOWER, DECORATIVE LIGHTING THAT MAY BE INSTALLED ALONG RIVEWAYS, SIDEWALKS, AND PARKING AREAS.
	D	ETACHED LIGHTING ON THE SITE WILL BE LIMITED TO 31 FEET IN HEIGHT.
•	M	ISCELLANEOUS:
۶/	d PC Ail [ 3Div	S PER THE PREVIOUSLY APPROVED CONDITIONAL PLAN, AND DUE TO THE PRESENCE OF SIGNIFICANT ENVIRONMENTAL FEATURES; WATER QUALITY OST CONSTRUCTION BUFFERS, TOPOGRAPHY AND OTHER ENVIRONMENTAL FACTORS, IN ADDITION TO THE FACT THAT THE EXTENSION OF BRANDON DRIVE WOULD BE THE THIRD CROSSING OF FUDA CREEK WITHIN 1,400 FEET, THE PETITIONER WILL REQUEST A MODIFICATION TO THE TO THE ISION REGULATIONS TO NOT REQUIRED THE EXTENSION OF BRANDON TRAIL DRIVE INTO THE SITE AS ALLOWED BY THE ALTERNATIVE COMPLIANCE SIONS OF THE SUBDIVISION REGULATIONS.
•	<u>A</u>	MENDMENTS TO THE REZONING PLAN:
	'NEF	UTURE AMENDMENTS TO THE REZONING PLAN (WHICH INCLUDES THESE DEVELOPMENT STANDARDS) MAY BE APPLIED FOR BY THE THEN OWNER OR RS OF THE APPLICABLE DEVELOPMENT AREA PORTION OF THE SITE AFFECTED BY SUCH AMENDMENT IN ACCORDANCE WITH THE PROVISIONS HEREIN F CHAPTER 6 OF THE ORDINANCE.
2.	В	INDING EFFECT OF THE REZONING APPLICATION:
	L, L	THIS REZONING PETITION IS APPROVED, ALL CONDITIONS APPLICABLE TO THE DEVELOPMENT OF THE SITE IMPOSED UNDER THE REZONING PLAN JNLESS AMENDED IN THE MANNER PROVIDED HEREIN AND UNDER THE ORDINANCE, BE BINDING UPON AND INURE TO THE BENEFIT OF THE DNER AND SUBSEQUENT OWNERS OF THE SITE AND THEIR RESPECTIVE HEIRS, DEVISEES, PERSONAL REPRESENTATIVES, SUCCESSORS IN INTEREST




PETITION #: 2017-042 CITY OF CHARLOTTE PETITIONER: ROCKY RIVER ROAD ASSOCIATES, LLC









2'-0" UTILITY EASEMENT




______ PROPOSED PRIVATE STREET 'D' - MAIN STREET SCALE: 1" = 10'-0" 
























VICINITY MAP

THE SCHEMATIC DEPICTIONS OF THE USES, PARKING AREAS, SIDEWALKS, STRUCTURES AND BUILDINGS, DRIVEWAYS, AND OTHER DEVELOPMENT MATTERS AND SITE ELEMENTS (COLLECTIVELY THE "DEVELOPMENT/SITE ELEMENTS") SET FORTH ON THE SCHEMATIC SITE PLAN SHOULD BE REVIEWED IN CONJUNCTION WITH THE PROVISIONS OF THESE DEVELOPMENT STANDARDS. THE LAYOUT, LOCATIONS, SIZES AND FORMULATIONS OF THE DEVELOPMENT/SITE ELEMENTS DEPICTED ARE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT/SITE ELEMENTS PROPOSED AND AS A RESULT MAY CHANGE AS LONG AS THE INTENT ILLUSTRATED IS MAINTAINED.

PETITION #: 2017-042 CITY OF CHARLOTTE PETITIONER: ROCKY RIVER ROAD ASSOCIATES, LLC

