

SURVEY DISCLAIMER
 A.G. ZOUTEWELLE SURVEYORS' SURVEY ISSUE DATE
 SEPTEMBER 25, 2007. PROVIDED BY ANDREW G. ZOUTEWELLE,
 1418 EAST FIFTH ST., CHARLOTTE, NC (704) 372-9444

LEGEND


SYMBOL

[Solid Grey Box]	BUILDING ENVELOPE
[Hatched Box]	GREENWAY EASEMENT CONVEYED TO MECKLENBURG COUNTY
[Dotted Box]	STORMWATER MITIGATION EASEMENT
[Cross-hatched Box]	DEDICATED TREE SAVE
[Dashed Line]	PROPOSED SIDEWALK CONNECTION
[Solid Line]	PROPOSED CURB & GUTTER

REZONING SUMMARY

PARCEL AREA : (067-031-04)	±15.42 AC
LAND TO BE CONVEYED TO MOREHEAD RIDGE : (BY MECKLENBURG COUNTY - PORTION OF 067-031-11)	±2.26 AC
REZONING SITE AREA : (GR025)	±17.69 AC
STORMWATER AND GREENWAY EASEMENT TO BE DEDICATED TO MECKLENBURG COUNTY: (ALONG FREEDOM DRIVE)	±3.76AC
TAX PARCEL #:	067-031-04 & A PORTION OF 067-031-11
EXISTING ZONING:	I-1
PROPOSED ZONING:	MUDD-O
EXISTING USE:	VACANT
PROPOSED USE:	MULTI-FAMILY RESIDENTIAL/ SINGLE-FAMILY ATTACHED RESIDENTIAL
MAXIMUM NUMBER OF DWELLING UNITS:	280
PROPOSED DENSITY:	15.82 UNITS/ACRE
MINIMUM SETBACK:	22' FROM THE FUTURE BACK OF CURB
MINIMUM SIDE YARD:	NONE; 10' BUILDING SEPARATION ADJACENT TO RESIDENTIAL USE
MINIMUM REAR YARD:	NONE; 10' BUILDING SEPARATION ADJACENT TO RESIDENTIAL USE
MAXIMUM BUILDING HEIGHT:	70'
PARKING REQUIRED:	1.5 SPACES/UNIT 1.5(280) = 420 SPACES
DEDICATED TREE SAVE:	REQUIRED: 2.65 AC (15%) PROVIDED: 3.00 AC (17%)

1. SEE SHEET RZ-200 FOR DEVELOPMENT STANDARDS
2. SEE SHEET RZ-200 FOR ZONING EXHIBIT



ColeJenest & Stone

Shaping the Environment
 Realizing the Possibilities

Land Planning
 Landscape Architecture
 Civil Engineering
 Urban Design

200 South Tryon Street, Suite 1400
 Charlotte, North Carolina 28202
 PH 704.376.1555 F 704.376.7851
 URL www.colejeneststone.com

GRIFFITH REAL ESTATE SERVICES

1944 BRUNSWICK AVE.
 CHARLOTTE, NC 28207

MOREHEAD RIDGE MULTI-FAMILY


1750 W MOREHEAD STREET
 CHARLOTTE, NC 28208

CONDITIONAL REZONING PLAN (2017-080)

Project No.
 4243

Issued
 03/24/17

Revised



RZ-100

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

1. General Provisions:

- A. These Development Standards form a part of the Rezoning Plan... B. The development of the Site will be governed by the Rezoning Plan... C. The parcels of land that comprise the Site may be recombined... D. The development and uses depicted on the Rezoning Plan are schematic... E. A maximum of 7 principal buildings may be located on the Site... F. The guardhouse at the vehicular entrance... G. The development of the buildings to be located on the Site may occur in phases... H. Future amendments to the Rezoning Plan and/or these Development Standards may be applied for by the then owner or owners of the Site in accordance with the provisions of Chapter 6 of the Ordinance.

2. Optional Provisions:

The optional provisions set out below shall apply to the development of the Site.

- A. Surface parking and vehicular maneuvering areas shall be permitted between Building 3 and the required setback from West Morehead Street... B. In the event that Building 4, Building 5 and/or Building 6 are not constructed prior to or concurrently with the construction of Building 1, Building 2 and/or Building 3... C. Surface parking and vehicular maneuvering areas shall be permitted between the buildings to be located on the Site and the required setback from Freedom Drive as generally depicted on Sheet RZ-100 of the Rezoning Plan.

3. Permitted Uses & Development Area Limitations:

- A. The Site may only be devoted to the uses set out below. (i) A residential community containing up to 280 dwelling units... (ii) Any single family attached dwelling units constructed on the Site shall be located in Building 4, Building 5 and/or Building 6... B. Up to three freestanding buildings containing single family attached dwelling units may be constructed along the Site's frontage on West Morehead Street... C. Until such time that Building 4, Building 5, and Building 6 are constructed, Petitioner shall install and maintain an urban green edge along the Site's frontage on West Morehead Street... D. At such time that Building 4, Building 5 and/or Building 6 are constructed, the relevant portion of the urban green edge may be removed to accommodate the building footprint and the construction of the building... E. Alternatively, in lieu of construction Building 6, Petitioner may extend Building 3 towards West Morehead Street in the manner depicted by the dashed lines on the Rezoning Plan.

4. Transportation/Access Notes:

- A. Vehicular access shall be as generally depicted on the Rezoning Plan... B. The alignment of the internal vehicular circulation areas and the driveways may be modified by the Petitioner to accommodate changes in traffic patterns... C. Notwithstanding anything contained herein to the contrary, the fire lane for the Site may connect to West Morehead Street as generally depicted on the Rezoning Plan... D. Subject to the approval of CDOT and NCDOT, and prior to the issuance of the first certificate of occupancy for a building constructed on the Site... E. In the event that the planned pedestrian refuge islands and the buffered bike lanes have been installed in West Morehead Street by the City at the time of the construction of any transportation improvements by Petitioner... F. All transportation improvements shall be constructed and approved prior to the issuance of the first certificate of occupancy for a building to be constructed on the Site or phased per the Site's development plan.

5. Architectural Standards:

- A. The maximum height in stories of Building 1, Building 2 and Building 3 shall be 5 stories... B. The maximum height in feet of Building 1, Building 2, and Building 3 shall be 70 feet... C. The maximum height in stories of Building 4, Building 5 and Building 6 shall be 4 stories with optional rooftop terraces... D. The maximum height in stories of the clubhouse/amenity building shall be 2 stories with an optional rooftop terrace... E. The minimum building separation between the buildings constructed on the Site shall be 10 feet... F. Dumpster and recycling areas will be enclosed on all four sides by an opaque wall or fence with one side being a hinged opaque gate... G. The colors of any retaining walls constructed on the Site shall be compatible to and complementary with the colors of the buildings to be constructed on the Site.

6. Streetscape, Buffers and Landscaping:

- A. Petitioner shall install a minimum 8 foot wide planting strip and a minimum 8 foot wide sidewalk along the Site's frontage on West Morehead Street as generally depicted on the Rezoning Plan.

7. Environmental Features:

- A. Development of the Site shall comply with the Charlotte City Council approved and adopted Post Construction Controls Ordinance... B. Development of the Site shall comply with the City of Charlotte Tree Ordinance... C. The tree save areas depicted on the Rezoning Plan are conceptual, and the actual locations of the tree save areas on the Site may vary from what is depicted on the Rezoning Plan.

8. Parks, Greenways, and Open Space:



- A. Prior to the issuance of the first certificate of occupancy for a building constructed on the Site, Petitioner shall convey a greenway and storm water easement to Mecklenburg County over that approximately 3.76 acre portion of the Site that is located along the northern boundary of the Site and is more particularly depicted on the Rezoning Plan.

9. Lighting:

- A. All freestanding lighting fixtures installed on the Site (excluding lower, decorative lighting that may be installed along the internal private drives and sidewalks, landscaping lighting and uplighting for the buildings.) shall be fully capped and shielded and the illumination downwardly directed so that direct illumination does not extend past any property line of the Site... B. The maximum height of any freestanding lighting fixture installed on the Site, including its base, shall not exceed 21 feet... C. Any lighting fixtures attached to the buildings to be constructed on the Site shall be decorative, capped and downwardly directed.

10. Binding Effect of the Rezoning Documents and Definitions:

- A. If this Rezoning Petition is approved, all conditions applicable to the use and development of the Site imposed under these Development Standards and the Rezoning Plan will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of Petitioner and the current and subsequent owners of the Site and their respective successors in interest and assigns... B. Throughout these Development Standards, the term "Petitioner" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof... C. Any reference to the Ordinance herein shall be deemed to refer to the requirements of the Ordinance in effect as of the date this Rezoning Petition is approved.



ColeJenest & Stone

Shaping the Environment Realizing the Possibilities

- Land Planning
Landscape Architecture
Civil Engineering
Urban Design

200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
ph 704.376.1555 fx 704.376.7851
url www.colejeneststone.com

GRIFFITH REAL ESTATE SERVICES

1944 BRUNSWICK AVE. CHARLOTTE, NC 28207

MOREHEAD RIDGE MULTI-FAMILY

1750 W MOREHEAD STREET CHARLOTTE, NC 28208

DEVELOPMENT STANDARDS

Project No. 4243

Issued 03/24/17

Revised



RZ-200

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.