

VICINITY MAP

NTS

1. GENERAL PROVISIONS
THESE DEVELOPMENT STANDARDS FORM A PART OF THE TECHNICAL DATA SHEET ASSOCIATED WITH THE REZONING PETITION FILED BY STONEHUNT DEVELOPMENT LLC TO REZONE A 6.8 ACRE SITE LOCATED WITHIN THE CHERRY COMMUNITY ADJACENT TO LUTHER ST., MAIN ST., ELI ST., ADVANT ST., AND BAXTER ST. (THE "SITE"). THE PURPOSE OF THIS PETITION IS TO REQUEST A REVISION TO THE REZONING OF THE SITE (THE SITE CURRENTLY UR-2 (CD) 2007-2A). THE REVISION OF THE CURRENT CD ZONING TO ALLOW THE CONSTRUCTION OF SINGLE FAMILY DETACHED HOMES ON THE SITE WITH DUPLEX UNITS ON THE CORNER LOTS IN SITE B & C. THE DEVELOPMENT OF THE SITE WILL BE GOVERNED BY THE TECHNICAL DATA SHEET, THESE DEVELOPMENT STANDARDS AND THE APPLICABLE PROVISIONS OF THE CITY OF CHARLOTTE ZONING ORDINANCE (THE "ORDINANCE"), UNLESS THE TECHNICAL DATA SHEET OR THESE DEVELOPMENT STANDARDS ESTABLISH MORE STRINGENT STANDARDS. THE DEVELOPMENT DEPICTED ON THE TECHNICAL DATA SHEET IS INTENDED TO REFLECT THE ROADWAY AND LOT CONFIGURATION PROPOSED FOR THE SITE. AREAS DEPICTED ARE SCHEMATIC AND ARE SUBJECT TO REFINEMENTS AS PART OF THE TOTAL DESIGN PROCESS. CHANGES TO THE REZONING PLAN NOT PERMITTED BY THE REZONING PLAN WILL BE REVIEWED AND APPROVED AS ALLOWED BY SECTION 6207 OF THE ORDINANCE.

2. PERMITTED USES
THE SITE A, B & C WILL BE DEVOTED TO RESIDENTIAL SINGLE-FAMILY DETACHED DWELLING UNITS, WITH DUPLEX UNITS ON LOTS 37 & 38 OF SITE B & C.
3. TRANSPORTATION
A. VEHICULAR ACCESS TO THE LOTS/UNITS SHALL BE AS GENERALLY DEPICTED ON THE TECHNICAL DATA SHEET. THE LOCATION OF VEHICULAR ACCESS POINT IS SUBJECT TO ANY MINOR MODIFICATIONS NECESSARY TO MEET THE CHARLOTTE DEPARTMENT OF TRANSPORTATION (CDOT) REQUIREMENTS FOR APPROVAL.
B. DRIVEWAYS AND PARKING PADS SHALL HAVE A MINIMUM LENGTH OF 20 FT. MEASURED FROM THE BACK OF THE SIDEWALK TO THE FACE OF THE GARAGE.
4. ARCHITECTURAL STANDARDS

- A. VINYL SIDING AS AN EXTERIOR BUILDING MATERIAL IS PROHIBITED. VINYL AS A BUILDING MATERIAL MAY BE USED ON WINDOWS AND DOOR TRIM.
B. ALL HOUSES WILL HAVE A FRONT PORCH WITH A MIN. 8 FEET IN DEPTH.
C. IDENTICAL HOUSE DESIGNS SHALL BE PROHIBITED ON ADJUTING LOTS.
5. STREETSCAPE AND LANDSCAPING
A. THE STREETSCAPE TREATMENT ALONG THE NEW PUBLIC STREETS WILL MEET OR EXCEED THE STANDARDS OF THE ORDINANCE AND INCLUDE LARGE MATURING TREES, SIDEWALKS OF AT LEAST SIX FEET IN WIDTH AND PLANTING STRIPS OF AT LEAST 8 FEET IN WIDTH. A 6' SIDEWALK SHALL BE PROVIDED ON LOTS FRONTING ON AN EXISTING STREET WHERE SIDEWALK DOES NOT PRESENTLY EXIST. ANY OTHER STREETSCAPE AND LANDSCAPING STANDARDS SHALL CONFORM TO THE ORDINANCE.
B. ANY SIDEWALK OUTSIDE OF THE ROADWAY RIGHT-OF-WAY SHALL BE WITHIN A MIN. 2 FOOT UTILITY EASEMENT (FROM BACK OF CURB).
C. A MINIMUM OF ONE PARKING SPACE AND A MAXIMUM OF 2 PARKING SPACES WILL BE PROVIDED FOR ALL UNITS IN THE FOLLOWING MANNER: 35% OF THE UNITS WILL BE SERVED BY A SIDE OR REAR ENTRY GARAGE, 45% WILL BE PROVIDED WITH A FRONT ENTRY ONE CAR GARAGE AND THE REMAINING 20% WILL HAVE A PARKING AREA PROVIDED IN THE FRONT OR SIDE OF THE UNITS. ALL GARAGES WILL BE RECESSED FROM THE FACE OF THE PRIMARY STRUCTURE BY A MINIMUM 2 FEET, AND PROVIDE FOR 20 FEET OF DRIVEWAY BETWEEN THE FACE OF THE GARAGE AND THE BACK OF THE SIDEWALK.


6. ENVIRONMENTAL FEATURES
(A) THE SITE SHALL COMPLY WITH ALL ENVIRONMENTAL REGULATIONS.
(B) THE PETITIONER SHALL COMPLY WITH THE ADOPTED POST CONSTRUCTION CONTROLS ORDINANCE.
(C) THE PETITIONER SHALL COMPLY WITH THE REQUIREMENTS OF THE CHARLOTTE TREE ORDINANCE.

7. LIGHTING
(A) ALL LIGHTING PROVIDED WILL BE DETACHED LIGHTING WITH A MAXIMUM HEIGHT OF 20'.

8. AMENDMENTS TO REZONING PLAN
FUTURE AMENDMENTS TO THE TECHNICAL DATA SHEET, OTHER SHEETS ACCOMPANYING THE PETITION AND THESE DEVELOPMENT STANDARDS MAY BE APPLIED FOR BY THE THEN OWNER OR OWNERS OF THE PARCEL WITHIN THE SITE INVOLVED IN ACCORDANCE WITH THE PROVISIONS OF SECTION 6207 OF THE ORDINANCE. ALL MODIFICATIONS OF ANY OF THESE PROVISIONS MUST COMPLY WITH SECTION 6207 OF THE ZONING ORDINANCE.

9. BINDING EFFECT OF THE REZONING DOCUMENTS AND DEFINITIONS
(A) IF THIS REZONING PETITION IS APPROVED, ALL CONDITIONS APPLICABLE TO DEVELOPMENT OF THE SITE IMPOSED UNDER THESE DEVELOPMENT STANDARDS AND THE TECHNICAL DATA SHEET WILL, UNLESS AMENDED IN THE MANNER PROVIDED UNDER THE ORDINANCE, BE BINDING UPON AND INURE TO THE BENEFIT OF THE PETITIONERS AND THE CURRENT AND SUBSEQUENT OWNERS OF THE SITE AND THEIR RESPECTIVE SUCCESSORS IN INTEREST AND ASSIGNS.
(B) THROUGHOUT THESE DEVELOPMENT STANDARDS, THE TERMS "PETITIONERS" AND "OWNER" OR "OWNERS" SHALL BE DEEMED TO INCLUDE THE HEIRS, DEVISEES, PERSONAL REPRESENTATIVES, SUCCESSORS IN INTEREST AND ASSIGNS OF THE PETITIONERS OR THE OWNER OR OWNERS OF THE SITE FROM TIME TO TIME WHO MAY


- BE INVOLVED IN ANY FUTURE DEVELOPMENT THEREOF.
(C) ANY REFERENCE TO THE ORDINANCE HEREIN SHALL BE DEEMED TO REFER TO THE REQUIREMENTS OF THE ORDINANCE IN EFFECT AS OF THE DATE THIS REZONING PETITION IS APPROVED.



SITE B & C DEVELOPMENT STANDARDS

SITE ACREAGE: 5.18 AC
TAX PARCEL NO.: 125-234-08,10,15,17,18,22,28
CURRENT ZONING CLASSIFICATION: UR-2 (CD) #2007-128
PROPOSED ZONING CLASSIFICATION: UR-2 (CD) SPA
EXISTING USE: SINGLE FAMILY (DUPLEX, TRIPLEX)
PROPOSED USE: SINGLE FAMILY (2 DUPLEX LOTS)
SITE ACREAGE: 1.00 AC
MAX. NO. OF UNITS PROPOSED: 10
MAX. PROPOSED DENSITY: 12.0 DU/A
PARKING PROPOSED: 1 SPACES (MIN) 2 SPACE (MAX) PER UNIT

UR-2 (CD) LOT DATA:
MIN. LOT SIZE = 3,000 SF
MIN. LOT WIDTH = 20'
MIN. SETBACK = 14' FROM B/C
MIN. SIDE YARD = 5'
MIN. REAR YARD = 10'
MAX. BUILDING HEIGHT = 40'
MAX. FLOOR AREA RATIO = 1.0
(400 SF OF OPEN SPACE WILL BE PROVIDED WITH EACH DUPLEX UNIT)



Public Hearing Map for Rezoning Petition #2014-024

The Grove at Cherry

City of Charlotte, Mecklenburg County, North Carolina
StoneHunt Development, 1313 N. Tryon St., Charlotte, NC 28203

Sheet No.

1


or

2

Scale: 1"=40'
Date: 12/17/13
Drawn By: MIK
Designed By: MIK
Job No.: 2213

Revisions:
1. REVISED PER B & C TO SINGLE FAMILY DETACHED
2. 2/11/14 REVISED PER STAFF COMMENTS, CHANGE HOUSE
AND DRIVE LAYOUT


KENNEY DESIGN
GROUP, PA



1316 GREENWOOD CLIFF
CHARLOTTE, NORTH CAROLINA 28204
PH: 704/377-6099 FAX: 704/377-6097
EMAIL: KENNEY@KENNEYDESIGN.COM

Engineering
Land Planning
Land Surveying

C-1986





Rezoning Petition # 2014-024
CHARLOTTE, NORTH CAROLINA | FEBRUARY 17, 2014