



1. The proposed retaining wall shall be "stepped down" to natural grade beyond the end of the sidewalk termination point in order to facilitate future extension of the sidewalk by Others..
2. The proposed sidewalk shall be terminated in such a manner that allows temporary ingress / egress to the sidewalk pending completion of the "future" portion by Others. The Developer and/or Contractor shall coordinate the sidewalk termination with the City Inspector. A "temporary" safety rail may be required at the terminating end of the sidewalk.

SIDEWALK MODIFICATION PLAN

Ballanmoor Subdivision

Pulte Group
11121 Carmel Commons Blvd. Suite 450, Charlotte, NC 28226

Sheet No.

SW-1

Of **1**

<h1>ENGINEERING</h1> <p>PCO / DETENTION / DRAINAGE PLAN</p>
<h1>EROSION CONTROL</h1> <p>NOTE: SCHEDULE PRE-CONSTRUCTION MEETING AT LEAST 48 HRS. PRIOR TO ANY LAND DISTURBING ACTIVITY USING THE ONLINE FORM AT http://development.charmeck.org</p>
<h1>URBAN FORESTRY</h1> <p>TREE ORDINANCE</p>
<h1>CDOT</h1>

APPROVED
By Brendan Smith at 4:44 pm, Nov 06, 2015