

**SURVEY DISCLAIMER**  
ALTA/ASCM LAND TITLE SURVEY ISSUED JUNE 6, 2010, REVISED JULY 29, 2016, PROVIDED BY R.B. PHARR & ASSOCIATES, P.A., 420 HAWTHORNE LANE, CHARLOTTE, NC 28204, (704) 376-2186.

LEGEND	
SYMBOL	
	PROPOSED SIDEWALK
	PROPOSED CURB & GUTTER
	STREET CONNECTION
	DRIVEWAY CONNECTION
	ZONING BOUNDARY
	UNDISTURBED P.C.C.O. BUFFER
	BUILDING & PARKING ENVELOPE
	TREE SAVE AREA

REZONING SUMMARY:	
PETITIONER:	TREVI PARTNERS, LLC 55 MIDTOWN PARK EAST MOBILE AL, 36606
PROPERTY OWNER:	TREVI PARTNERS, LLC 55 MIDTOWN PARK EAST MOBILE AL, 36606
REZONING SITE AREA:	15.86± ACRES
TAX PARCEL #:	051-081-26
EXISTING ZONING:	CC, UR-C (CD)
PROPOSED ZONING:	UR-C (CD)
EXISTING USE:	VACANT
PROPOSED USE:	MULTI-FAMILY RESIDENTIAL
BUILDING SETBACK: (ALONG US 29)	30' FROM BACK-OF-CURB
BUILDING SETBACK: (INTERNAL PUBLIC STREETS)	14' FROM BACK-OF-CURB
MIN. SIDE YARD:	5'
MIN. REAR YARD:	20'
MAX. BUILDING HEIGHT:	FOUR (4) STORIES
MAX. FLOOR AREA RATIO: (F.A.R.)	3.0
PARKING RATIO:	1.25/UNIT MINIMUM
DEDICATED TREE SAVE:	REQUIRED: 2.38 AC (15%) PROVIDED: 4.62 AC
MAX. NO. DWELLING UNITS:	275
PROPOSED DENSITY:	17.34 DUA

- GENERAL REZONING NOTES**
- SEE SHEET RZ-200 FOR DEVELOPMENT STANDARDS
  - SEE SHEET RZ-200 FOR ZONING EXHIBIT
  - SEE SHEET RZ-200 FOR PUBLIC AND PRIVATE STREET SECTIONS

**ColeJenest & Stone**  
Shaping the Environment  
Realizing the Possibilities

Land Planning  
+ Landscape Architecture  
+ Civil Engineering  
+ Urban Design

200 South Tryon Street, Suite 1400  
Charlotte, North Carolina 28202

p+ 704 376 1555 f+ 704 376 7851  
url+ www.colejeneststone.com

**SOUTHLAND CAPITAL REALTY GROUP, LLC**

55 MIDTOWN PARK EAST  
MOBILE, AL 36606

**TREVI VILLAGE MULTI-FAMILY REZONING**  
12220 U.S. HIGHWAY 29  
CHARLOTTE, NC 28262

**REZONING PLAN**

Project No.  
4004

Issued  
05/23/16

Revised  
08/22/16 - FIRST REVIEW STAFF COMMENTS

SCALE: 1"=100'  
0 50' 100' 200'

**RZ-100**

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A., The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2016 ©

**PETITION #: 2016-107**



August 22, 2016

## SITE DEVELOPMENT DATA:

--ACREAGE: 15.86 ± ACRES

--TAX PARCEL #S: 051-081-26

--EXISTING ZONING: CC, UR-C (CD)

--PROPOSED ZONING: UR-C (CD)

--EXISTING USES: VACANT

--PROPOSED USES: UP TO 275 MULTI-FAMILY DWELLING UNITS TOGETHER WITH ACCESSORY USES, AS ALLOWED IN THE UR-C ZONING DISTRICT

--MAXIMUM BUILDING HEIGHT: BUILDING HEIGHT WILL BE LIMITED TO FOUR (4) STORIES. ARCHITECTURAL FEATURES SUCH AS SPIRES, MANSARDS, DOMES, AND THE LIKE AS WELL AS ROOF TOP MECHANICAL EQUIPMENT, AND SCREENS OR DEVICES USED TO SCREEN ROOF TOP STRUCTURES OR EQUIPMENT WILL BE ALLOWED AND WILL NOT BE CONSIDERED PART OF THE ALLOWED FOUR (4) STORY BUILDING HEIGHT.

--PARKING: 1.25 SPACES PER UNIT MINIMUM

--TREE SAVE: A MINIMUM OF 15% OF THE SITE WILL BE ESTABLISHED AS TREE SAVE AREAS AS DEFINED IN CHARLOTTE TREE ORDINANCE. TREE SAVE WILL BE REVIEWED FOR ENTIRE UNIFIED DEVELOPMENT.

## 1. GENERAL PROVISIONS:

a. THE DEVELOPMENT STANDARDS FORM A PART OF THE REZONING PLAN ASSOCIATED WITH THE REZONING PETITION FILED BY TREVI VILLAGE, LLC ("THE PETITIONER") TO ACCOMMODATE THE DEVELOPMENT OF AN APPROXIMATELY 15.86 ACRE SITE LOCATED AT 12220 U.S. HIGHWAY 29 ("THE SITE") WITH A MULTI-FAMILY RESIDENTIAL COMMUNITY THAT COULD CONTAIN UP TO 275 MULTI-FAMILY DWELLING UNITS.

b. DEVELOPMENT OF THIS SITE WILL BE GOVERNED BY THE ATTACHED REZONING PLAN AND THESE DEVELOPMENT STANDARDS (COLLECTIVELY REFERRED TO AS THE "REZONING PLAN") AS WELL AS THE APPLICABLE PROVISIONS OF THE CITY OF CHARLOTTE ZONING ORDINANCE ("THE ORDINANCE"). SUBJECT TO THE OPTIONAL PROVISIONS SET OUT BELOW, THE REGULATIONS ESTABLISHED UNDER THE ORDINANCE FOR THE UR-C (CD) ZONING DISTRICT CLASSIFICATION SHALL GOVERN DEVELOPMENT TAKING PLACE ON THE SITE.

c. THE REZONING AREA WILL BE A PART OF A LARGER UNIFIED DEVELOPMENT WHICH WILL INCLUDE THE PROPERTY EAST OF PUBLIC ROAD 'A' (PARCEL NOS. 051-091-09, 051-091-10, 051-091-11, 051-091-12) AS SHOWN ON THE REZONING PLAN. THIS PROPERTY WAS REZONED UNDER THE APPROVED PETITION NO. 2010-047. THIS PROPERTY WILL BE RE-COMBINED AS PART OF THE SUBDIVISION REVIEW AND APPROVAL PROCESS.

d. THE REZONING PLAN DEPICTIONS OF THE USES, PARKING AREAS, SIDEWALKS, STRUCTURES AND BUILDINGS, AND OTHER SITE ELEMENTS SET FORTH OF THE REZONING PLAN SHOULD BE REVIEWED IN CONJUNCTION WITH THE PROVISIONS OF THESE DEVELOPMENT STANDARDS. THE ULTIMATE LAYOUT, LOCATIONS AND SIZES OF THE DEVELOPMENT AND SITE ELEMENTS DEPICTED ON THE REZONING PLAN ARE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT AND SITE ELEMENTS PROPOSED, AND THE MAY BE ALTERED OR MODIFIED IN ACCORDANCE WITH THE SETBACK, YARD AND BUFFER REQUIREMENT SET FORTH ON THIS REZONING PLAN AND THE DEVELOPMENT STANDARDS, PROVIDED, HOWEVER, ANY SUCH ALTERATION AND MODIFICATIONS SHALL NOT MATERIALLY CHANGE THE OVERALL DESIGN INTENT DEPICTED ON THE REZONING PLAN. CHANGES TO THE REZONING PLAN NOT PERMITTED BY THE ORDINANCE, SINCE THE PROJECT HAS NOT UNDERGONE THE DESIGN DEVELOPMENT AND CONSTRUCTION PHASES, IT IS INTENDED THAT THIS REZONING PLAN PROVIDE FOR FLEXIBILITY IN ALLOWING SOME ALTERATIONS OR MODIFICATIONS FROM THE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT/SITE ELEMENTS. THEREFORE, THERE MAY BE INSTANCES WHERE MINOR MODIFICATIONS WILL BE ALLOWED WITHOUT REQUIRING THE ADMINISTRATIVE AMENDMENT PROCESS PER SECTION 6.207 OF THE ORDINANCE. THESE INSTANCES WOULD INCLUDE CHANGES TO GRAPHICS IF THEY ARE:

i. EXPRESSLY PERMITTED BY THE REZONING PLAN (IT IS UNDERSTOOD THAT IF A MODIFICATION IS EXPRESSLY PERMITTED BY THE REZONING PLAN IT IS DEEMED A MINOR MODIFICATION FOR THE PURPOSES OF THESE DEVELOPMENT STANDARDS); OR,

ii. MINOR AND DON'T MATERIALLY CHANGE THE OVERALL DESIGN INTENT DEPICTED ON THE REZONING PLAN; OR

iii. MODIFICATIONS TO MOVE STRUCTURES GRAPHICALLY DEPICTED ON THE REZONING PLAN CLOSER TO ADJACENT PROPERTIES BUT NO CLOSER THAN THE "EXTERNAL BUILDING LINE" (IN THIS CASE THE EXTERNAL SETBACKS, SIDE OR REAR YARDS) INDICATED ON SHEET RZ-100.

THE PLANNING DIRECTOR WILL DETERMINE IF SUCH MINOR MODIFICATIONS ARE ALLOWED PER THIS AMENDED PROCESS, AND IF IT IS DETERMINED THAT THE ALTERATION DOES NOT MEET THE CRITERIA DESCRIBED ABOVE, THE PETITIONER SHALL THEN FOLLOW THE ADMINISTRATIVE AMENDMENT PROCESS PER SECTION 6.207 OF THE ORDINANCE. IN EACH INSTANCE, HOWEVER, SUBJECT TO THE PETITIONER'S APPEAL RIGHTS SET FORTH IN THE ORDINANCE.

## 2. OPTIONAL PROVISIONS:

THE FOLLOWING OPTIONAL PROVISIONS SHALL APPLY TO THE SITE:

a. TO ALLOW THE OFF-STREET SERVICE AND DELIVERY SPACES TO BE REDUCED TO ONE (1) LOADING SPACE FOR BUILDINGS 1-6 AND ONE (1) LOADING SPACE FOR BUILDINGS 7-8.

b. TO ALLOW PARKING AREAS TO BE LOCATED BETWEEN BUILDING NUMBER TWO (2) AND PUBLIC STREET 'A' AS GENERALLY DEPICTED ON THE REZONING PLAN WITH THE USE OF A MINIMUM 36" TALL MASONRY SCREEN WALL.

## 3. PERMITTED USES, DEVELOPMENT AREA LIMITATIONS:

a. THE SITE MAY BE DEVELOPED WITH UP TO 275 MULTI-FAMILY DWELLING UNITS TOGETHER WITH ACCESSORY USES ALLOWED IN THE UR-C (CD) ZONING DISTRICT.

## 4. TRANSPORTATION IMPROVEMENTS AND ACCESS:

## i. PROPOSED IMPROVEMENTS

a. ACCESS TO THE SITE WILL BE FROM U.S. HIGHWAY 29 AS GENERALLY DEPICTED ON THE REZONING PLAN.

b. MINOR ADJUSTMENTS IN THE LOCATION OF THE POSSIBLE CONNECTION CAN BE MADE IN CONSULTATION WITH THE PLANNING DEPARTMENT DURING THE PLANNED MULTI-FAMILY REVIEW AND APPROVAL PROCESS;

c. SUBJECT TO THE PROVISIONS AND DESIGN DESCRIBED IN THE SECTION ABOVE, THE PLACEMENTS AND CONFIGURATIONS OF VEHICULAR ACCESS POINTS ARE SUBJECT TO ANY MINOR MODIFICATIONS BY CDDT/NCDDT, REQUIRED TO ACCOMMODATE THE FINAL SITE DEVELOPMENT AND CONSTRUCTION PLANS AND TO ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY THE CDDT/NCDDT IN ACCORDANCE WITH PUBLISHED STANDARDS.

d. THE ALIGNMENT OF THE INTERNAL VEHICULAR CIRCULATION AND DRIVEWAYS MAY BE MODIFIED BY PETITIONER TO ACCOMMODATE CHANGES IN TRAFFIC PATTERNS, PARKING LAYOUTS, AND ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY CDDT IN ACCORDANCE WITH PUBLISHED STANDARDS.

## ii. STANDARDS, PHASING AND OTHER PROVISIONS.

a. CDDT/NCDDT STANDARDS. ALL OF THE FOREGOING PUBLIC ROADWAY IMPROVEMENTS WILL BE SUBJECT TO THE STANDARDS AND CRITERIA OF CDDT AS APPLICABLE. IT IS UNDERSTOOD THAT SUCH IMPROVEMENTS MAY BE UNDERTAKEN BY THE PETITIONER ON ITS OWN OR IN CONJUNCTION WITH OTHER DEVELOPMENT OR ROADWAY PROJECTS TAKING PLACE WITHIN THE AREA, BY WAY OF A PRIVATE/PUBLIC PARTNERSHIP EFFORT OR OTHER PUBLIC SECTOR PROJECT SUPPORT.

b. RIGHT-OF-WAY AVAILABILITY. IT IS UNDERSTOOD THAT SOME OF THE PUBLIC ROADWAY IMPROVEMENTS REFERENCED ABOVE MAY NOT BE POSSIBLE WITHOUT THE ACQUISITION OF ADDITIONAL RIGHT OF WAY. IF AFTER THE EXERCISE OF DILIGENT GOOD FAITH EFFORTS OVER A MINIMUM OF A 60 DAY PERIOD, THE PETITIONER IS UNABLE TO ACQUIRE ANY LAND NECESSARY TO PROVIDE FOR ANY SUCH ADDITIONAL RIGHT OF WAY UPON COMMERCIALLY REASONABLE TERMS AND PRICES AT MARKET PRICES, THEN CDDT, THE CITY OF CHARLOTTE, ENGINEERING DIVISION OR OTHER APPLICABLE AGENCY, DEPARTMENT OR GOVERNMENTAL BODY AGREE TO PROCEED WITH ACQUISITION OF ANY SUCH LAND. IN SUCH EVENT, THE PETITIONER SHALL REMBURSE THE APPLICABLE AGENCY, DEPARTMENT OR GOVERNMENTAL BODY FOR THE COST OF ANY SUCH ACQUISITION PROCEEDINGS INCLUDING COMPENSATION PAID BY THE APPLICABLE AGENCY, DEPARTMENT OR GOVERNMENTAL BODY FOR ANY SUCH LAND AND THE EXPENSES OF SUCH PROCEEDINGS. FURTHERMORE, IN THE EVENT PUBLIC ROADWAY IMPROVEMENTS REFERENCED IN SUBSECTION A. ABOVE ARE DELAYED BECAUSE OF DELAYS IN

THE ACQUISITION OF ADDITIONAL RIGHT-OF-WAY AS CONTEMPLATED HEREIN AND SUCH DELAY EXTENDS BEYOND THE TIME THAT THE PETITIONER SEEKS TO OBTAIN A CERTIFICATE OF OCCUPANCY FOR BUILDING(S) ON THE SITE IN CONNECTION WITH RELATED DEVELOPMENT PHASING DESCRIBED ABOVE, THEN THE PETITIONER WILL WORK WITH CITY STAFF TO DETERMINE A PROCESS TO ALLOW THE ISSUANCE OF CERTIFICATES OF OCCUPANCY FOR THE APPLICABLE BUILDINGS; PROVIDED, HOWEVER, PETITIONER CONTINUES TO EXERCISE GOOD FAITH EFFORTS TO COMPLETE THE APPLICABLE ROAD-WAY IMPROVEMENTS. IN SUCH EVENT THE PETITIONER MAY BE ASKED TO POST A LETTER OF CREDIT OR A BOND FOR ANY IMPROVEMENTS NOT IN PLACE AT THE TIME SUCH A CERTIFICATE OF OCCUPANCY IS ISSUED TO SECURE COMPLETION OF THE APPLICABLE IMPROVEMENTS.

c. ALTERNATIVE IMPROVEMENTS. CHANGES TO THE ABOVE REFERENCED ROADWAY IMPROVEMENTS CAN BE APPROVED THROUGH THE ADMINISTRATIVE AMENDMENT PROCESS UPON THE DETERMINATION AND MUTUAL AGREEMENT OF PETITIONER, CDDT, AND THE PLANNING DIRECTOR AS APPLICABLE. PROVIDED, HOWEVER, THE PROPOSED ALTERNATE TRANSPORTATION IMPROVEMENTS PROVIDE (IN THE AGGREGATE) COMPARABLE TRANSPORTATION NETWORK BENEFITS TO THE IMPROVEMENTS IDENTIFIED IN THIS PETITION.

d. THE PRIVATE MALLARD CREEK WASTEWATER TREATMENT PLANT ACCESS ROAD IMPROVEMENTS AND ACCESS COORDINATION SHALL BE IMPLEMENTED TO CHARLOTTE WATER'S SATISFACTION PRIOR TO ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY FOR THE FIRST NEW BUILDING COMPLETED ON THE SITE.

e. ALL PUBLIC TRANSPORTATION IMPROVEMENTS SHALL BE CONSTRUCTED AND APPROVED PRIOR TO ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY FOR THE FIRST NEW BUILDING COMPLETED ON THE SITE.

f. THE PETITIONER WILL DEDICATE IN FEE-SIMPLE AND CONVEY ALL PUBLIC RIGHTS OF WAY TO THE CITY OF CHARLOTTE PRIOR TO ISSUANCE OF THE FIRST CERTIFICATE OF OCCUPANCY FOR THE FIRST NEW BUILDING COMPLETED ON THE SITE.

## 5. ARCHITECTURAL STANDARDS:

a. PREFERRED EXTERIOR BUILDING MATERIALS - ALL PRINCIPAL AND ACCESSORY BUILDING ABUTTING A PUBLIC OR PRIVATE STREET SHALL COMPRISE A MINIMUM OF 30% OF A BUILDING TOTAL FACADE (EXCLUSIVE OF WINDOWS, DOORS AND BALCONIES).

i. BRICK

ii. NATURAL STONE (OR SYNTHETIC EQUIVALENT)

iii. OTHER EQUIVALENT OR BETTER MATERIAL APPROVED BY THE PLANNING DIRECTOR OR HIS/HER DESIGNEE

b. PROHIBITED EXTERIOR BUILDING MATERIALS - THE FOLLOWING EXTERIOR BUILDING MATERIALS ARE SPECIFICALLY PROHIBITED:

i. VINYL SIDING (EXCEPT FOR SOFFITS AND TRIM INCLUDING WINDOW AND DOOR TRIM)

ii. CONCRETE MASONRY UNITS (CMU) NOT ARCHITECTURALLY FINISHED.

c. BUILDING PLACEMENT AND DESIGN - BUILDING PLACEMENT AND SITE DESIGN SHALL FOCUS ON AND ENHANCE THE PEDESTRIAN ENVIRONMENT THROUGH THE FOLLOWING STANDARDS:

i. BUILDING STREET FRONTAGE - BUILDINGS SHALL BE ARRANGED AND ORIENTED TO FRONT ALONG ALL NETWORK REQUIRED STREETS (PUBLIC OR PRIVATE STREETS) AS DEFINED BY THE SUBDIVISION ORDINANCE, EXCEPT FOR U-03 & U-05 STREET TYPES DEFINED BY THE URBAN STREET DESIGN GUIDELINES.

ii. BUILDINGS SHALL FRONT A MINIMUM OF 50% OF THE TOTAL STREET FRONTAGE ON THE SITE (EXCLUSIVE OF DRIVEWAYS, PEDESTRIAN ACCESS POINTS, USABLE OPEN SPACE, TREE SAVE AREAS, NATURAL AREAS, AND/OR TREE RE-PLANTING AREAS.

iii. PARKING LOTS SHALL NOT BE LOCATED BETWEEN ANY BUILDING AND ANY PUBLIC OR PRIVATE STREET, EXCEPT AS NOTED IN THE REZONING PLAN.

iv. DRIVEWAYS FOR PRIVATE RESIDENTIAL GARAGES AND/OR PARKING SHALL BE PROHIBITED ON ALL NETWORK REQUIRED STREETS.

d. BUILDING MASSING & HEIGHT - BUILDING MASSING SHALL BE DESIGNED TO BREAK UP LONG, MONOLITHIC BUILDING FORMS THROUGH THE FOLLOWING STANDARDS:

i. BUILDING MASSING - BUILDINGS EXCEEDING 120 FEET IN LENGTH SHALL INCLUDE MODULATIONS OF THE BUILDING MASSING/FACADE PLANE (RECESS, PROJECTION, ARCHITECTURAL TREATMENT, ETC.). MODULATIONS SHALL BE A MINIMUM OF 10 FEET WIDE AND SHALL EXTEND OR RECESS A MINIMUM OF 5 FEET, EXTENDING THROUGH ALL FLOORS. MODULATIONS WILL OCCUR EVERY 10 FEET.

ii. BUILDING HEIGHT - PER THE ZONING ORDINANCE.

e. ARCHITECTURAL ELEVATION DESIGN - ARCHITECTURAL ELEVATIONS SHALL BE DESIGNED TO CREATE VISUAL INTEREST THROUGH THE FOLLOWING STANDARDS:

i. VERTICAL MODULATION AND RHYTHM - BUILDING ELEVATIONS SHALL BE DESIGNED WITH RECOGNIZABLE VERTICAL BAYS OR ARTICULATED ARCHITECTURAL FACADE FEATURES. THE BAYS AND FEATURES MAY INCLUDE, BUT NOT LIMITED TO A COMBINATION OF EXTERIOR WALL OFFSETS, PROJECTIONS, AND/OR RECESSES, PLASTER, AND CHANGE IN MATERIALS.

ii. BUILDING BASE - BUILDINGS SHALL BE DESIGNED WITH A RECOGNIZABLE ARCHITECTURAL BASE. A MINIMUM OF THREE ELEVATIONS OF EACH BUILDING WILL BE ARTICULATED WITH A WAINSCOT OF PREFERRED EXTERIOR BUILDING MATERIALS LISTED ABOVE A MINIMUM OF THREE (3) FEET IN HEIGHT.

iii. BLANK WALLS - BUILDING ELEVATIONS FACING STREETS SHALL NOT HAVE EXPANSES OF BLANK WALLS EXCEEDING 20 FEET.

iv. ARCHITECTURAL FEATURES SUCH AS, BUT NOT LIMITED TO, BANDING, MEDALLIONS, OR DESIGN FEATURES OR MATERIALS WILL BE PROVIDED TO AVOID A STERILE, UNARTICULATED BLANK TREATMENT OF SUCH WALLS.

f. ROOF FORM AND ARTICULATION - ROOF FORM AND ROOFLINES SHALL BE DESIGNED TO AVOID THE APPEARANCE OF A LARGE MONOLITHIC ROOF STRUCTURE THROUGH THE FOLLOWING STANDARDS:

i. LONG ROOFLINES (PITCHED OR FLAT) SHALL AVOID CONTINUOUS EXPANSES WITHOUT VARIATION BY INCLUDING CHANGES IN HEIGHT AND/OR ROOF FORM (E.G. DORMERS, GABLES, ETC.)

ii. FOR PITCHED ROOFS THE MAXIMUM PITCH SHALL BE 4:12 (FOUR FEET IN VERTICAL HEIGHT FOR EVERY 12 FEET IN HORIZONTAL LENGTH), EXCLUDING BUILDINGS WITH A FLAT ROOF AND PARAPET WALLS.

iii. ROOF-TOP HVAC AND RELATED MECHANICAL EQUIPMENT WILL BE SCREENED FROM PUBLIC VIEW AT GRADE FROM THE NEAREST STREET AND FROM THE NEAREST SINGLE-FAMILY STRUCTURE IF LOCATED ON ROOF.

g. SERVICE AREA SCREENING - SITE SERVICE AREAS (DUMPSTERS, REFUSE AREAS, RECYCLING AREAS, STORAGE) SHALL BE SCREENED FROM VIEW THROUGH THE FOLLOWING STANDARDS:

i. SERVICE AREAS WILL BE SCREENED BY A MINIMUM 30 PERCENT MASONRY MATERIAL

ii. UTILITY STRUCTURES NEED TO BE SCREENED ARCHITECTURALLY OR WITH EVERGREEN PLANT MATERIAL

iii. WALLS SHALL BE DESIGNED TO MATCH AND COMPLEMENT THE BUILDING ARCHITECTURE OF THE RESIDENTIAL BUILDINGS OF THE SUBJECT PROPERTY.

## 7. ENVIRONMENTAL FEATURES:

iii. THE SITE SHALL COMPLY WITH THE CHARLOTTE CITY COUNCIL APPROVED AND ADOPTED POST CONSTRUCTION CONTROLS ORDINANCE.

ii. THE LOCATION, SIZE, AND TYPE OF STORM WATER MANAGEMENT SYSTEMS DEPICTED ON THE REZONING PLAN ARE SUBJECT TO REVIEW AND APPROVAL AS PART OF THE FULL DEVELOPMENT PLAN SUBMISSION AND ARE NOT IMPLICITLY APPROVED WITH THIS REZONING. ADJUSTMENTS MAY BE NECESSARY IN ORDER TO ACCOMMODATE ACTUAL STORM WATER TREATMENT REQUIREMENTS AND NATURAL SITE DISCHARGE POINTS.

## 8. OPEN SPACE/TREE SAVE AREAS/GREENWAY DEDICATION:

ii. OPEN SPACE/TREE SAVE AREAS EQUALING 15% OF THE SITE AREA WILL BE PROVIDED. THE OPEN SPACE/TREE SAVE AREAS DEPICTED ON THE REZONING PLAN MAY BE RELOCATED TO OTHER LOCATION ON THE SITE IF THE AREA OF THE SITE TO BE DEDICATED TO COUNTY PARKS AND RECREATION FOR GREENWAY PURPOSES THE AREA AND ACCESS MANAGEMENT AS GENERALLY DEPICTED ON THE REZONING PLAN.

## 9. LIGHTING:

a. ALL NEW ATTACHED AND DETACHED LIGHTING SHALL BE FULLY SHIELDED DOWNWARDLY DIRECTED AND FULL CUT OFF FIXTURE TYPE LIGHTING EXCLUDING LOWER, DECORATIVE LIGHTING THAT MAY BE INSTALLED ALONG THE DRIVEWAYS, SIDEWALKS, AND PARKING AREAS.





b. DETACHED LIGHTING ON THE SITE, EXCEPT STREET LIGHTS LOCATED ALONG PUBLIC STREETS, WILL BE LIMITED TO 21 FEET IN HEIGHT TO ALLOW BASE.

## 10. AMENDMENTS TO THE REZONING PLAN:

a. FUTURE AMENDMENTS TO THE REZONING PLAN (WHICH INCLUDES THESE DEVELOPMENT STANDARDS) MAY BE APPLIED FOR BY THE THEN OWNER OR OWNERS OF THE APPLICABLE DEVELOPMENT AREA PORTION OF THE SITE AFFECTED BY SUCH AMENDMENT IN ACCORDANCE WITH THE PROVISIONS HEREIN AND OF CHAPTER 6 OF THE ORDINANCE.

## 11. BINDING EFFECT OF THE REZONING APPLICATION:

a. IF THIS REZONING PETITION IS APPROVED, ALL CONDITIONS APPLICABLE TO THE DEVELOPMENT OF THE SITE IMPOSED UNDER THE REZONING PLAN WILL, UNLESS AMENDED IN THE MANNER PROVIDED HEREIN AND UNDER THE ORDINANCE, BE BINDING UPON AND INURE TO THE BENEFIT OF THE PETITIONER AND SUBSEQUENT OWNERS OF THE SITE OR DEVELOPMENT AREAS, AS APPLICABLE, AND THEIR RESPECTIVE HEIRS, DEVISEES, PERSONAL REPRESENTATIVES, SUCCESSORS IN INTEREST OR ASSIGNS.



## ColeJenest &amp; Stone

Shaping the Environment  
Realizing the Possibilities

Land Planning  
+  
Landscape Architecture  
+  
Civil Engineering  
+  
Urban Design

200 South Tryon Street, Suite 1400  
Charlotte, North Carolina 28202

p+ 704 376 1555 f+ 704 376 7851  
url+ www.colejeneststone.com

SOUTHLAND  
CAPITAL REALTY  
GROUP, LLC

55 MIDTOWN PARK EAST  
MOBILE, AL 36606

TREVI VILLAGE  
MULTI-FAMILY  
REZONING

12220 U.S. HIGHWAY 29  
CHARLOTTE, NC 28262

DEVELOPMENT  
STANDARDS

Project No.

4004

Issued

05/23/16

Revised

08/22/16 - FIRST REVIEW STAFF COMMENTS



## RZ-200

The drawings, the project manual and the design shown therein are instruments of ColeJenest & Stone, P.A. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2016 ©

PETITION #: 2016-107























**PRELIMINARY**  
**FOR COORDINATION &**  
**REVIEW ONLY**



FLOOD CERTIFICATION  
THIS IS TO CERTIFY THAT THE SUBJECT PROPERTY  
LOCATED IN A SPECIAL FLOOD HAZARD AREA  
MAPS PREPARED BY THE FEDERAL EMERGENCY  
AGENCY, FEDERAL INSURANCE ADMINISTRATION  
MARCH 2, 2009  
COMMUNITY PANEL NO: 371045 9800J

THIS IS TO CERTIFY THAT ON THE 06 DAY OF JUNE 20 10 AN ACTUAL SURVEY WAS MADE UNDER MY SUPERVISION OF THE PROPERTY SHOWN ON THIS PLAN, AND THAT THE BOUNDARY LINES AND THE IMPROVEMENTS, IF ANY, ARE AS SHOWN HEREON. THIS PLAN MEETS THE MINIMUM STANDARDS OF PRACTICE FOR LAND SURVEYING IN NORTH CAROLINA, BOARD RULE, 1600 (2) NCAC 56 AND THE RATIO OF PRECISION DOES NOT EXCEED AN ERROR OF CLOSURE OF ONE (1) FOOT PER 10,000 FEET OF PERIMETER SURVEYED NOR 20 SECONDS TIMES THE SQUARE ROOT OF THE NUMBER OF ANGLES TURNED.

NOTES:  
1. SEE SHEET 1 OF 3 FOR ALL NOTE INFORMATION



THIS SHEET IS PART OF A SET OF 3 AND ALL SHEETS MUST  
BE TOGETHER FOR COMPLETE SURVEY

SHEET 3 OF 3

LTA/ACSM LAND TITLE SURVEY PREPARED FOR  
**TREVI PARTNERS, LLC**  
 NORTH TRYON STREET/US HIGHWAY 29  
 CITY OF CHARLOTTE, MECKLENBURG COUNTY, NC  
 DB. 21291, PG. 483  
 TAX PARCEL NO: 051-091-09 & 051-081-26

R.B. PHARR &amp; ASSOCIATES, P.A.

CREW:	DRAWN:	REVISED:	SCALE:	DATE:	FILE NO. W-3916
TR	CW		1" = 100'/20'	JUNE 06, 2010	JOB NO. 76218

PLOTTED: 8/1/2014  
C:\RR PHARR\85319\85319.D\W