





TP 229-152-36
NOW OR FORMERLY
GEORGE LATIMER
DB 6377 PG 186
ZONED R-3

1. Garage entrances must be at least 20 feet from streets or sidewalks.
2. Buffers will be undisturbed wherever possible.
3. Screening fence will be located within the interior half of the buffer.
4. Swim Buffer will be undisturbed except for the upland zone, the road crossing and the rear porch for Unit 2.
5. Pedestrian scale lighting will be provided throughout the development.

- ③ 1.5" BITUMINOUS CONCRETE SURFACE COURSE, TYPE SF9.5A
OR 1.5" BITUMINOUS CONCRETE SURFACE COURSE, TYPE 1-2.
- ④ 6" COMPACTED AGGREGATE BASE COURSE OR 4"
BITUMINOUS CONCRETE BASE COURSE, TYPE B25.0B
OR 4" BCBC TYPE HB.
- ⑤ CURB AND GUTTER (REFERENCE 10.17A AND B)



DRAWN BY AFF			DWG FILE NAME 06304SP		DATE 08-13-2007	
SURVEYED BY GJG		DESIGNED BY AFF		SHEET NUMBER 1		
JOB NUMBER 06304		FILE NUMBER 854				