
# Morrison - Tract 3

Developer - Morrison Place, LLC 1523 Elizabeth Avenue, Suite 220 Charlotte, NC 28204



VICINITY MAP not to scale

Index of Drawings:								
		Issue Date						
RZ-CS	Cover Sheet	02.13.09						
RZ-2	Existing Conditions Plan	02.13.09						
RZ-2	Illustrative Site Plan	02.13.09						
RZ-3	Technical Data Sheet	02.13.09						
RZ-4	Development Standards	02.13.09						
	,							
		:						



1 - 404 5/25/6 550 - 11 - 7(14)56 1.8

This drawing and the design shown are the prope of Little Diversified Architectural Consulting. T reproduction, copying or other use of this drawi without their written consent is prohibited and a infringement will be subject to legal action.

G 71.1 4000

Rezoning Petition 2009-022

12/28/08

NO. REASON DATE

Per Staff Review Comments 02/13/09


PRINCIPAL IN CHARGE
David Powlen, RLA LEED
PROJECT MANAGER
Mark Van Sickle, RLA
DESIGN TEAM
MVS

Morrison Place Tract 3 Rezoning

101.5632.00

**COVER SHEET** 

RZ-CS



#### ADJACENT OWNERS

- V HAYDEN JR MCMAHON AND BARBARA N MCMAHON
  2501 MORROCROFT LN
  CHARLOTTE, NC 28211
- D SCOTT WELTON AND LAURA H WELTON
  2515 MORROCROFT LN
  CHARLOTTE, NC 28211
- 3 STEFAN R LATORRE AND CINDY LATORRE 2525 MORROCROFT LN CHARLOTTE, NC 28211
- 4 LOUIS D ROOT
  2535 MORROCROFT LN
  CHARLOTTE, NC 28211
- JONATHAN KENT GANZERT AND KAREN MONTAQUILA 2545 MORROCROFT LN CHARLOTTE, NC 28211
- 6 MICHAEL D MCLEAN AND BARBARA W MCLEAN
  2553 MORROCROFT LN
  CHARLOTTE, NC 28211
- 7 DANIEL G REGAN AND JOYCE F REGAN
  2557 MORROCROFT LN
  CHARLOTTE, NC 28211
- 8 MORROCROFT APARTMENTS INC 2633 RICHARDSON DR CHARLOTTE, NC 28211
- 9 GRUBB PROPERTIES
  1523 ELIZABETH AVENUE
  SUITE 220
  CHARLOTTE, NC 28204
- 10 BETTY J CARTER L/T BUMGARDNER
  2524 LEMON TREE LN
  CHARLOTTE, NC 28211
- 11 MARK S LERNER AND ALISON R LERNER
  2600 LEMON TREE LN
  CHARLOTTE, NC 28211
- 12 LARRY E PRICE AND LYNDA A PRICE 2612 LEMON TREE LN CHARLOTTE, NC 28211
- JOSEPH VITALE AND STRAWN CATHCART
  2624 LEMON TREE LANE
  CHARLOTTE, NC 28211
- EDWARD P IMBROGNO AND ANNETTE M IMBROGNO
  2700 LEMON TREE LN
  CHARLOTTE, NC 28211

GRAPHIC SCALE

( IN FEET )
1 inch = 100 ft.



www.littleonline.com

This drawing and the design shown are the property of Little Diversified Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

© Little 2009 —

Rezoning Petition 2009-022

12/28/08

VIGIC	NS.												
<b>)</b> .	RE	ASC	NC										DATE
	Pe	or S	ta	F	(9)	/ie	W I	Co	·	ne	nte		12/13/0
				,	,					,			
										,			
					,		•						
												-	
		,	٠						,				


PROJECT II AM
PRINCIPAL IN CHARGE
David Powlen, RLA LEED
PROJECT MANAGER
Mark Van Sickle, RLA

Morrison Place
Tract 3
Rezoning


101.5632.00

EXISTING CONDITIONS

RZ-1



## PRIVATE STREETS "A" & "B"




PROPOSED R-IN / R-OUT DRIVEWAY ACCESS 'C' FROM PETITION 2004-015


2000 N. 2000 2000 N. 2000 N. 2000 2000 N. 20

**EXISTING R-IN / R-OUT** 

ACCESS 'B' FROM PETITION 2004-015

EXISTING R-IN / R-OUT DRIVEWAY ACCESS 'A' FROM PETITION 2004-015





GRAPHIC SCALE ( IN FEET ) 1 inch = 100 ft.

www.littleonline.com

This drawing and the design shown are the property of Little Diversified Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

Rezoning Petition 2009-022

12/28/08

12/28/08													
V 10. EAI210	RE. Pe	ASC r S	}	DATE 12/13/09									
<u> </u>				•			•	,	•	•	•	•	12/13/0
·													
									,		,		
												,	
	,												
								•					

PROJECT HAM
PRINCIPAL IN CHARGE
David Powlen, RLA LEED PROJECT MANAGER
Mark Van Sickle, RLA DESIGN TEAM MVS


Morrison Place Tract 3 Rezoning

101.5632.00


**TECHNICAL** DATA SHEET

RZ-2


120' MAX.




ARCHITECTURAL CHARACTER




ARCHITECTURAL CHARACTER



ARCHITECTURAL CHARACTER



ARCHITECTURAL CHARACTER





1: 704.525.6350 1: 704.561.8700 www.littleonline.com

This drawing and the design shown are the property of Little Diversified Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

—© Little 2009

Rezoning Petition 2009-022

12/29/09

12/28/08											
NO.	REASON Per Staff Review Comments	DATE 12/13/0									
		<b>————</b>									

PROJECT TEAM
PRINCIPAL IN CHARGE
David Powlen, RLA LEED
PROJECT MANAGER
Mark Van Sickle, RLA
DESIGN TEAM

Morrison Place
Tract 3
Rezoning

101.5632.00

PROJECT NUMBER

ILLUSTRATIVE SITE PLAN

RZ-3

#### **DEVELOPMENT STANDARDS-REZONING PETITION NO. 2009-22**

#### A Portion of the Morrison Development, Sharon and Colony Roads

#### General Provisions

These Development Standards form a part of the Technical Data Sheet associated with the MUDD-O Site Plan Amendment filed by Grubb Properties (Sheet RZ-2) to accommodate several revisions to the previously approved development plan for Tract 3 of the Morrison development at SouthPark, a mixed use, pedestrian-friendly village center located on the northwesterly corner of the intersection formed by Sharon Road and Colony Road. Tract 3 contains approximately 7.95 acres located within the easterly portion of Morrison, all as more particularly described on the Technical Data Sheet (hereinafter referred to as the "Site").

Development of the Site will be governed by the Technical Data Sheet (Sheet RZ-2), the Illustrative Site Plan (Sheet RZ-3), these Development Standards, and the applicable provisions of the City of Charlotte Zoning Ordinance (the "Ordinance"), subject to the Optional Provisions set forth under Section A below. Unless the Technical Data Sheet or these Development Standards establish more stringent standards, the regulations established under the Ordinance for the Mixed Use Development District (MUDD) zoning classification, shall govern all development taking place on this Site.

The exact alignments of internal streets and driveways have not been determined and are subject to final design and engineering plans. Minor modifications or alternations of these alignments may therefore take place during design development and construction phases.

The exact locations of buildings and parking areas have also not been determined and are subject to final design and engineering plans. Accordingly, flexibility shall be granted to the Petitioner / Developer to make adjustments to the precise building sizes and locations shown on the Illustrative Site Plan during final design changes. However, buildings shall be located within the building envelope depicted on the Technical Data Sheet, their placements shall be generally consistent with the locations depicted on the Illustrative Site Plan and they shall satisfy all other Ordinance standards.

Locations of trees, plantings, open space and hardscape amenities may be altered or modified to accommodate Site plan configuration changes. Parking layouts may also be modified to accommodate final building locations and parking spaces may be located on surface or within parking decks to the extent permitted by the Ordinance.

All such changes are subject to approval per Section 6.206(2) of the Ordinance.

#### A. Optional Provisions

The Petitioner requests a variation from the signage provisions under the Ordinance for the MUDD Zoning classification in order to allow for detached, ground-mounted signs in the locations indicated on Sheet RZ-3. (See Signs provision below). The sign located at Access B will be no more than 5 feet in height as measured from the final grade and no greater than 65 square feet in size. The area of the copy of this sign shall not exceed 50 square feet. The sign located at Access C will be no more than 4 feet in height as measured from the final grade and no greater than 32 square feet in size. The area of the copy of this sign shall not exceed 28 square feet.

#### B. Permissible Development and Uses

- 1. Permitted Uses: The Site may be devoted to any combination of residential uses, health/ medical/ wellness/ fitness uses, continuing care retirement community uses and ground floor commercial (retail and/or office) uses, along with any accessory uses and structures clearly incidental and related to the permitted principal uses or structures, as allowed in the MUDD Zoning Classification and subject to any restrictions and provisions hereinafter provided.
- 2. Permitted Development: Development of the Site will be subject to the following limitations and provisions:
- a. no more than 195 for sale residential units may be developed on the Site.
- b. no more than 30,000 square feet of floor area devoted to health/medical, wellness/ fitness uses may be developed on the Site.
- c. continuing care retirement community units and/or beds may be developed in lieu of undeveloped residential units as permitted under Paragraph B. 2. a. above at a rate not to exceed two independent living units for each for sale residential unit that is not developed on or transferred from the Site and 3 assisted living/skilled nursing units and/or beds for each for sale residential unit that is not developed on or transferred from the Site.
- d. no more than 20,000 square feet of ground floor commercial uses may be developed on the Site, subject to the following restrictions:
- i. individual retail establishments may not exceed 8,500 square feet of floor area;
- ii. no commercial uses may be located outside the area generally depicted for commercial development on Sheet RZ-3.

The uses permitted under Paragraphs B. 2. a, b and c of these Development Standards may be located above the commercial uses.

#### 3. Building Descriptions / Restrictions

Any portion of any building located within 125 feet of the property line of the abutting Village of Morrocroft development (See Illustrative Site Plan ) shall not exceed two stories or 35 feet in height measured from the average grade of the building.

Any portion of any building located within 125 feet to 150 feet of the property line of the abutting Village of Morrocroft development (See Illustrative Site Plan) shall not exceed three stories or 55 feet in height measured from the average grade of the building.

Any portion of any building located within 150 feet to 300 feet of the property line of the abutting Village of Morrocroft development (See Illustrative Site Plan) shall not exceed five stories or 65 feet in height measured from the average grade of the building.

Any portion of any building located beyond 300 feet of the property line of the abutting Village of Morrocroft development (See Illustrative Site Plan) shall not exceed 120 feet in height measured from the average grade of the building.

Certain residential units which back up to The Village of Morrocroft property line and fall within the area designated on Sheet RZ-2 are required to be single family or duplex residential units.

## 4. Other Use Conditions and Limitations

Accessory uses to residential development include but are not limited to, laundry rooms, leasing offices, property management offices, pools, clubhouses, fitness rooms, storage/janitorial rooms, lobbies, concierge areas, loading docks, trash/recycling areas, and outdoor patios/courtyards/plazas all of which shall not be included in the calculation of the maximum floor areas or residential units noted above.

Accessory uses to the commercial development are limited to loading docks, outdoor patios/courtyards/plazas and trash/recycling areas all of which shall not be included in the calculation of the maximum floor areas or allowable commercial square footage noted above.

Surface, on-street, and/or structured parking facilities may be constructed within the Site. Any surface level parking or structured parking facilities shall not be included in the calculations of any applicable maximum floor area ratio.

Any for sale residential units permitted under Paragraph B. 2. a. above which are not converted to other uses in accordance with the provisions of Paragraphs B. 2. c. and d. above or developed on this Site may be transferred from this Site to Tract 1 of Morrison (see previous Rezoning Petition No. 2004-015) subject to the maximum residential unit count established for the Morrison site in Rezoning Petition No. 2004-015. Additional residential units may not be transferred to this Site.

## C. Setbacks, Side Yards, Rear Yards and Edge Treatments

- 1. All buildings constructed within the Site shall satisfy or exceed the setback, rear yard and side yard requirements established under the Ordinance for the Mixed Use Development District (MUDD), and under the Technical Data Sheets.
- 2. No building may be located on the Site any closer than 45 feet to the Site's common line with the Village of Morrocroft (See Sheet RZ-2).
- 3. The edge treatment along the Village of Morrocroft property line (see Sheet RZ-2) shall include a landscaped strip which is at least 20 feet in width that includes, at a minimum, sufficient planting materials to satisfy the following standards:

8 trees per 100 feet

and

20 shrubs per 100 feet

This 20 foot landscaped strip may be installed within the 45 foot rear yard established on Sheet RZ-2, and Paragraph C.2, above.

4. The walking trail/bike path described in Paragraph G.3. below may meander throughout the 45 foot rear yard established on Sheet RZ-2 and under C.2. above.

## D. Architectural Controls

- 1. Buildings constructed on the Site along Sharon Road will utilize four-sided architecture and contain windows and doors that face these streets and these doors shall be operational. Large expanses of solid walls for these buildings will be avoided through the introduction of articulated facades and other specially designed architectural elements in accordance with the Ordinance.
- 2. Dumpster areas will be enclosed on all four sides by an opaque wall with one side being a hinged opaque gate. If one or more sides of a dumpster area adjoin a side or rear wall of a building, then the side or rear wall may be substituted for a side. Dumpsters will be screened in accordance with the Ordinance. No dumpsters will be located within 100 feet of the northerly or easterly property lines abutting residential zoning classifications.
- 3. All residential units presently existing on the Site may be either demolished or preserved subject to being included in the count to determine the maximum number of units allowed. All such buildings which are preserved may be up-fitted without bringing them into compliance with Section 9.8506 of the Ordinance.
- 4. Subject to its being able to obtain approvals to do so from the utilities involved, the Petitioner will cause all new utility lines (not including relocations or replacements of existing lines) installed on the Site to be buried.
- 5. The building materials for all elevations shall include brick and glass as the primary construction material with accents of stucco, architectural concrete block, EIFS, natural or manufactured stone, pre-cast concrete, and architectural metals. At least 60% of the exterior opaque vertical surfaces below the eaves (not including the doors and windows) of all buildings constructed on the Site will be composed of brick.

## E. Phases

Any or all portions of the development permitted on the Site may be constructed at any point subject to Section P below. Temporary interim parking may be provided throughout the Site subject to the standards of the Ordinance.

#### F. Streetscape Treatment

- 1. The streetscape treatment along Sharon Road will conform to Section 9.8506 of the Ordinance and include either existing or proposed large or small maturing trees and supplemental shrubbery.
- 2. The Petitioner shall make every reasonable effort to preserve all existing trees six inches in caliper and larger located within the 30-foot setback along Sharon Road with the exception of trees which may be removed in order to install driveways across the setbacks. The Petitioner will utilize tree protection measures such as barricades during the construction process and tree maintenance measures such as automatic irrigation in an effort to preserve such trees.
- 3. The Petitioner shall cause to be installed on the Site six-foot wide sidewalks and eight-foot wide planting strips along its frontage on Sharon Road as new development occurs adjacent to the street.
- 4. Sidewalks of at least 5 feet in width shall be provided on at least one side of all internal streets and extending from the interior of the Site out to the sidewalk system along Sharon Road and Colony Road.
- 5. Large maturing trees, spaced approximately 40 feet on center, shall be provided along both sides of all internal streets.

#### G. Screening and Landscaping Areas

- 1. The Petitioner shall cause to be installed within the setback areas along Sharon Road, trees and other materials in accordance with the City of Charlotte Tree Ordinance and shall thereafter maintain or cause to be maintained all such materials (including replacement of all dead or dying trees and/or other plant materials).
- 2. Internal areas of the Site shall be landscaped in accordance with the requirements of the City Code.
- 3. The landscape area along the rear project edge shall conform to the standards and treatments delineated on the Illustrative Site Plan and will include large or small maturing trees and a walking trail/bike path. Upon its completion, the walking trail/bike path will be open and available for use by the general public. This path shall be at least 10 feet in width through the back portion of the Site.
- 4. All roof mounted mechanical equipment will be screened from view from adjoining public rights-of-way and abutting properties as viewed from grade.
- 5. Storm water retention areas will be located to the rear of the Site and each of these areas will contain heavy landscaping and seating.6. All other screening and landscaping shall meet or exceed the standards of the Ordinance.

## H. Parking and Loading

- 1. Off street parking and loading will meet or exceed the minimum standards established under the Ordinance.
- 2. Parking areas may include surface parking and/or structured parking. Surface parking areas will be screened in accordance with the Ordinance. Developer is allowed to vary the location, quantity and configuration of the proposed parking areas identified on the Illustrative Site Plan in accordance with the provisions of Section 6.207 of the Ordinance. Structured parking will be treated architecturally or screened by buildings and/or landscaping in order to avoid large expanses of blank walls.
- 3. Angled, parallel or perpendicular parking may be provided along internal streets within the Site.
- 4. Bicycle parking will be provided on Site as required by the Ordinance.

#### I. Lightin

- 1. The Petitioner shall provide pedestrian-scale lighting along Sharon Road, along the internal streets, at vehicular entrances to the Site from Sharon Road and along the walking trail. The Petitioner shall thereafter maintain or cause to be maintained all such lighting. All pedestrian-scale lighting will be shielded with full cut off.
- 2. The maximum height of any freestanding lighting fixture erected on the Site (other than streetlights on public rights-of-way) including its base, shall not exceed 20 feet. All parking lot lighting shall be designed such that direct illumination does not extend past any property line.
- 3. No wall pack light fixtures will be allowed on any structures constructed on the Site. However, wall-mounted decorative light fixtures such as sconces are permitted.

#### J. Signs (See Optional Provisions above)

- 1. A master signage and graphics system will be implemented throughout the Site.
- 2. Any detached signage shall be ground-mounted or monument-style. Commercial detached signage will be no more than 5 feet in height as measured from the final grade and no more than 65 square feet in size. The area of the copy on any Commercial detached signage shall not exceed 50 square feet per sign. Residential detached signage will be no more than 4 feet in height as measured from the final grade and no more than 32 square feet in size. The area of the copy on any residential detached signage shall not exceed 28 square feet per sign.

#### K. Access Point

1. Access C will be limited to a right-in, right-out driveway, as generally indicated on the Technical Data Sheet. Placement and configuration of access is subject to any minor modification required to accommodate final site and architectural construction plans and designs and to any adjustments required for approval by the Charlotte Department of Transportation.

#### L. Fire Protection

Adequate fire protection in the form of fire hydrants will be provided to the Charlotte Fire Marshal's specifications. Plans for each building will be submitted to the Fire Marshal's office for approval before the construction of that building commences.

## M. Storm Water Management

All impervious areas on the Site in excess of 146,000 square feet (the existing coverage) shall be treated for water quality per the Post Construction Controls Ordinance. The Petitioner will utilize standard BMPs to provide treatment of stormwater runoff from the impervious areas in excess of the existing coverage, including, but not limited to, all parking areas. The BMPs shall be designed and constructed in accordance with the latest revision of the Charlotte-Mecklenburg County BMP Design Manual to achieve 85% Total Suspended Solids removal for the runoff generated from the first 1-inch of rainfall from the impervious areas in excess of the existing coverage. As an option to installing standard BMPs, the Petitioner shall be permitted to install pervious concrete (or pavers) according to the specifications from Charlotte Storm Water Services in lieu of the BMPs to treat parking areas. If the developer chooses this method of treating the storm water runoff, Petitioner will provide a storm system design and sampling manholes as required by Charlotte Storm Water Services to allow for monitoring of the runoff from the impervious areas in excess of the existing coverage.

The Petitioner will provide stormwater volume control for the 1-year, 24-hour storm for the runoff generated from the first 1-inch of rainfall from the impervious areas in excess of the existing coverage. Runoff volume drawdown time shall be a minimum of 24-hours but not more than 120 hours. As an option to installing standard BMPs, the Petitioner shall be permitted to install pervious concrete (or pavers) according to the specifications from Charlotte Storm Water Services in lieu of the BMPs to treat parking areas. If the developer chooses this method of treating the storm water runoff, Petitioner will provide a storm system design and sampling manholes as required by Charlotte Storm Water Services to allow for monitoring of the runoff from the areas in excess of the existing coverage.

The Petitioner shall limit the peak runoff at each storm water outfall to the existing conditions for the 2-year, the 10-year, and 25-year storms.

## N. Interior Streets

All internal streets will be private.

## O. Transportation Commitments:

- 1. The Petitioner shall construct Access C (a new right in/right out driveway to Sharon Road closest to Morrocroft Lane) prior to the issuance of any certificates of occupancy for any new development on the Site.
- 2. Until the design of the roadway/intersection improvement described in this Paragraph 0.1. above is completed and reviewed / approved by CDOT, no site plans may be approved for any building/driveway permits.

## P. CATS Waiting Pad

The Petitioner will construct a CATS Waiting Pad and provide a bicycle rack along Sharon Road in the area generally depicted on Sheet RZ-3.

## Q. Amendments to Rezoning Plan

Future amendments to the Technical Data Sheets, the Illustrative Site Plan and these Development Standards may be applied for by the then Owner or Owners of the parcel or parcels within the Site involved in accordance with the provisions of Chapter 6 of the Ordinance.

## R. Binding Effect of the Rezoning Documents and Definitions

- 1. If this Rezoning Petition is approved, all conditions applicable to development of the Site imposed under the Technical Data Sheets will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of the Petitioner and the current and subsequent owners of the Site and their respective successors in interest and assigns.
- 2. Throughout these Development Standards, the terms, "Petitioner" and "owner" or "owners" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of the Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof.

## DIVERSIFIED ARCESTS STAR ALL CONSULTING

5815 Westpark Drive Charlotte, NC 2821 T: 704.525 6350 F: 704 561 870

www.littleonline.com

This drawing and the design shown are the property of Little Diversified Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

—© Little 2009 ——

Rezoning Petition 2009-022

12/28/08

NO. REASON DATE
Per Staff Review Comments 12/13/

. . . . . . . . .

David Powlen, RLA LEED
PROJECT MANAGER
Mark Van Sickle, RLA
DESIGN TEAM
MVS

Morrison Place

PRINCIPAL IN CHARGE

Tract 3
Rezoning

ROJECT NUMBER

101.5632.00
SHEET TITLE
DEVELOPMENT

STANDARDS

R7-4