


NOT TO SCALE



DEVELOPMENT DATA TABLE

- A. Site Acreage : 0.50 acres.
- B. Tax Parcels included in Rezoning : 125-24-104
- C. Existing Zoning : R-12 MF
- D. Proposed Zoning : O-2 (CD)
- E. Existing and Proposed Uses : Residential / Parking Lot
- F. Number of Residential Units by Housing Type : N/A
- G. Residential Density : N/A
- H. Square Footage of Non-Residential Uses by Type : N/A
- I. Floor Area Ratio : 1.0
- J. Maximum Building Height : 40 Feet
- K. Number and/or Ratio of Parking Spaces : 26 Spaces Surface Parking Lot
- L. Amount of open space : N/A

1. GENERAL PROVISIONS

- A. The development of the Site will be governed by the Rezoning Plan, these Development Standards and the applicable provisions of the City of Charlotte Zoning Ordinance (the "Ordinance") for the O-2 zoning district unless more stringent standards are established by these Development Standards or this Rezoning Plan.
- B. Alterations/modifications to the Rezoning Plan and these Development Standards may be applied for by the then Owner or Owners of the Site in accordance with the provisions of Section 6.207 of the Ordinance.

2. PERMITTED USES

The Site may be devoted only to the uses set out below.

- A. Off-street parking that serves the adjacent Ronald McDonald House use and facility. As depicted on the Rezoning Plan, a maximum of 26 parking spaces may be located on the Site. Temporary outdoor uses related to the functions of the Ronald McDonald House.
- B.
- A. Vehicular access shall be as generally depicted on the Rezoning Plan. The placement and configuration of the access point are subject to any minor modifications required by the Charlotte Department of Transportation and/or the North Carolina Department of Transportation.

4. STREETScape, BUFFERS, AND LANDSCAPING

- A. A 16 foot Class C buffer shall be established along portions of the Site's boundary lines as depicted on the Rezoning Plan, which buffer shall conform to the standards of Section 12.302 of the Ordinance. In the event that an adjacent parcel of land is either rezoned to a zoning district or devoted to a use that eliminates or reduces the buffer requirements on the Site, then the Petitioner may reduce or eliminate, as the case may be, the 16 foot Class C buffer. The Petitioner may reduce the width of the 16 foot Class C buffer by 25% by installing a wall or fence pursuant to Section 12.302(8) of the Ordinance.
- B. Screening and landscaping shall meet the requirements of the Ordinance.

5. LIGHTING

- A. All freestanding lighting fixtures installed on the Site shall be fully capped and shielded and the illumination downwardly directed so that direct illumination does not extend past any property line of the Site.
- B. The maximum height of any freestanding lighting fixture installed on the Site shall be 12 feet.

6. BINDING EFFECT OF THE REZONING PETITION

If this Rezoning Petition is approved, all conditions applicable to the development and/or use of the Site imposed under this Rezoning Plan will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of Petitioner and the current and subsequent owners of the Site and their respective successors in interest and assigns. Throughout these Development Standards, the terms, "Petitioner" and "owner" or "owners" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof.

SETBACK AND YARDS

Development of the Site shall comply with the setback, side yard and rear yard requirements of the O-2 zoning district.

RONALD McDONALD HOUSE OF CHARLOTTE PARKING LOT

CHARLOTTE, NC

PROJECT TEAM  
PRINCIPAL IN CHARGE  
D. POWLEN, RLA  
PROJECT MANAGER  
D. POWLEN, RLA  
DRAWN BY  
K. RAMSEY

NO.	REVISION	DATE
1	PER CITY COMMENTS	02/22/13

REZONING PLAN

PROJECT NO.	101.0026.00
DATE	12/21/12
SHEET NUMBER	RZ-1

CONSULTANTS:  
LITTLE DIVERSIFIED ARCHITECTURAL CONSULTING  
5815 WESTPARK DRIVE  
CHARLOTTE, NORTH CAROLINA 28217  
(704) 525-6350

PETITIONER:  
THE RONALD McDONALD HOUSE OF CHARLOTTE  
1613 E. MOREHEAD STREET  
CHARLOTTE, NORTH CAROLINA 28207  
(704) 335-1191


TAX PARCEL #:  
125-24-104

SITE DATA:

TOTAL ACREAGE:	±0.5015 AC.
EXISTING ZONING:	R-12 MF
PROPOSED ZONING:	O-2 (CD)
PROPOSED USE:	26 SPACE SURFACE PARKING LOT
MAXIMUM BUILDING HEIGHT:	40 FEET
TREE SAVE PERCENTAGE:	REQUIRED: 15% MIN., PROVIDED: 20 %
REQUIRED SETBACK:	FRONT YARD - 30 FEET RIGHT SIDE YARD - 5 FEET LEFT SIDE YARD - 5 FEET REAR YARD - 20 FEET FRONT YARD - 50 FEET RIGHT SIDE YARD - 5 FEET LEFT SIDE YARD - 5 FEET REAR YARD - 20 FEET
PROVIDED SETBACK:	

EXISTING ZONING: R-12 MF  
PROPOSED ZONING: O-2 (CD)  
TOTAL ACREAGE: ±0.5015 AC.

REZONING PETITION #: 2013-028



1" = 20'-0"

SECOND SUBMITTAL 02/22/2013

RECEIVED  
By mcalato at 11:30 am, Feb 22, 2013